Con 12-1-1 Doc # 13707





1601 Golden Aspen Drive • Suite 103 • Ames, Iowa 50010 • 800.433.3469 • www.foxeng.com

December 4, 2007

Ms. Nina Koger, Lead Engineer Energy & Waste Management Bureau Iowa Department of Natural Resources 502 East 9th Street Des Moines, Iowa 50319

RE:

2007 Annual Groundwater Quality Report

City of Muscatine C&D Landfill

70-SDP-4-78C

P.N. 6008

Ms. Koger:

Find attached a copy of the 2007 Annual Groundwater Quality Report for the City of Muscatine C&D Landfill.

A copy of this data has been forwarded to Ms. Laura Liegois, Solid Waste Manager and Field Office #6 as required by the Permit.

Sincerely,

FOX ENGINEERING ASSOCIATES, INC.

200 Whip

Todd Whipple, CPG Project Manager

22471 DEC05'07 AM10:23

FOR THE

MUSCATINE C&D LANDFILL PERMIT 70-SDP-4-78C MUSCATINE, IOWA

by:
FOX Engineering, Inc.
1601 Golden Aspen Drive, Suite 103
Ames, Iowa 50010
(515) 233-0000



November 19, 2007

Ms. Nina Koger, Lead Engineer IDNR – Energy & Waste Management Bureau Wallace State Office Building 502 E. 9th Street Des Moines, Iowa 50319

RE: Muscatine C&D Landfill

CLOSURE PERMIT # 70-SDP-4-78C

FOX PN 6008-07B.320

Dear Ms. Koger:

This Annual Groundwater Quality Report has been prepared in accordance with IAC 567-113.26(8) and the Closure Permit (Appendix A).

1. ANNUAL REPORT SUPPLEMENT

This report supplement addresses the numbered information requests set out in the December 1, 2004 IDNR Letter and reiterated in the February 14, 2006 IDNR Letter (Appendix A).

The geology and hydrogeology are described in the Hydrogeologic Investigation Report (HIR) and Hydrologic Monitoring System Plan (HMSP) prepared by Green Environmental Services, Inc., February, 1994 (Appendix B).

Previous land use is believed to be an undeveloped ravine.

The former solid waste stream consisted of a single demoltion/construction debris event within the City of Muscatine. This event occurred in the late 1970's.

- 2) The approved monitoring network is illustrated in Sheet 1.
- 3) The Water Table Contour Map is included as Sheet 1.
- 4) A Potentiometric Map of the Regional Aquifer is not included. The potentiometric surface slopes south toward the Mississippi River.
- 5) It appears that shallow groundwater mimics the topography and slopes to the southeast. The upgradient water table well (MW-6) does not appear to be impacted by the construction demolition fill. The remainder of the monitoring network appears to be situated to effectively detect any migration to downgradient wells.
- 6) Current water quality data is included in Appendix C. Current and historic water quality is included in Appendix D.

Page 1 of 4 Pages

- 7) The upgradient well (MW-6) appears to be functioning effectively as valid upgradient sampling point based on both the hydrogeology and the water quality results. The approved Hydrologic Monitoring System Plan (HMSP) does not include surface water monitoring points.
- 8) Control limits are calculated in the spreadsheets included in Appendix D. Comparison of the downgradient water quality data to the calculated limits is presented in the text below.
- 9) Graphical representations of water quality data, calculated control limits, and EPA Maximum Contaminant Limits (MCL's) are included in Appendix D. Comparison of the downgradient water quality data to the calculated limits is presented in the text below.
- 10) Discussion of the groundwater quality data is presented in the text below.
- 11) A discussion of the surface water quality data is not applicable.
- 12) Conclusions and recommendations are included in a separate section at the end of this report.

ANNUAL REPORT

- 1. <u>Effects on Surface Water:</u> Surface water at the site is controlled by vegetation and City street infrastructure. There are no surface water points being sampled at the present time.
- 2. Effects on Groundwater: A summary of analytical data for each monitoring well in the HMSP and the Analytical Reports for the past year are included as Attachment C. A summary of the statistical computations for the upgradient Water Table Well (MW-6) is included in the Concentration versus Time spreadsheets in Attachment D. The concentrations of the various compounds detected in each well are graphed over time versus the statistical limits calculated in the upgradient well. The graphs are included in the spreadsheets in Attachment D.

The monitoring system includes monitoring wells intersecting the water table surface within glacial tills. The effects to the groundwater are discussed below.

Monitoring wells comprising the Hydrologic Monitoring System Plan (HMSP) include MW 6 (upgradient) and MW 2, 3, 4, and 7 (downgradient). Analytical results from upgradient monitoring well MW-6 indicate historically detected concentrations of chloride, COD, iron, nitrogen ammonia, phenol, and TOX. The presence of the compounds in the upgradient well suggest that the compounds are endemic to the region, or, conversely, that an upgradient source of the compounds exists. It is noted that a cemetery exists upgradient of the site.

Detected concentrations in all monitoring wells are below the Primary Drinking Water MCL. The upgradient well (MW-6) and each of the downgradient wells MW-2, MW-3, MW-4, and MW-7 exhibit iron concentrations in excess of the Secondary Drinking Water MCL. Similarly, the chloride concentration at MW-3 exceeded the Secondary Drinking Water MCL in January, 1996; April, 1998; and October, 1998.

Those compounds that exceed the calculated statistical limit, but not the MCL are summarized by well as follows:

MW-2 - COD (10/99), TOX (10/96), phenol (10/98 & 10/00).

MW-3 - iron, chloride, nitrogen ammonia (7/95), COD (10/96), TOX (10/96), phenol (10/98).

MW-4 - chloride (prior to 4/01), COD (4/99), TOX (10/96 & 10/98), phenols(10/98).

MW-7 - iron (10/98), TOX (10/96), phenol (10/98).

Due to the presence of detectable concentrations of each of the listed compounds in the upgradient well, the elevated levels in the downgradient wells listed above are not interpreted as an indication of a leachate release into groundwater.

The detection of a compound above statistical limits during a single episode or during isolated episodes are not interpreted to represent a persistent leachate release. The interpretation is made that detection above the statistical limits during a single event, or during isolated episodes represents anomalous conditions in the well, the site conditions, or in the sampling activities.

Each parameter will continue to be routinely sampled and evaluated in accordance with the Special Provisions of the Permit.

3. Monitoring Well Maintenance and Performance Evaluation: Monitoring Well Performance Evaluation Reports dated April, 1999 and August, 2004 were prepared and submitted in accordance with IAC 567-113.21. The report concluded that the integrity of all MW's was intact, and that no changes in the HMSP were recommended. Monitoring well reevaluation is tentatively scheduled for the summer of 2009, and should again include all monitoring wells included in HMSP.

Review of the water elevation data for 2007 does not indicate excessive variability compared to historic water elevation data. Water elevation data is summarized in Attachment E. Based on the available water elevation data, the assessment of well conditions, and the hydrologic conditions at the site, the semi-annual water level measurements are interpreted to be sufficient to gauge notable changes in the site hydrology.


Flow paths are illustrated on the Groundwater Contour Map included as Figure 1.


4. Leachate Control Plan: This landfill is currently exempt from providing and implementing a leachate control system plan as per the Closure Permit. The conditional exemption is common in many Closure Permits at sites that were closed prior to the requirement for leachate collection systems. Our recent semi-annual Engineering's inspections have not revealed leachate seeps at the site.

5. **Explosive Gas Monitoring:** Explosive gas monitoring ceased at the site in 1998 based on authorization by IDNR in Provision 2, Permit Amendment #1, dated September 15, 1998 (Attachment A).

6. Recommendations:

- a. Continue routine monitoring of the HMSP monitoring wells and re-evaluate in the Annual Groundwater Quality Report due November 30, 2008.
- b. Continue water elevation measurements on a semi-annual basis.
- c. Continue Engineer's inspections on a semi-annual basis.
- d. Continue to monitor the integrity of the landfill cap.





FOX 1601 G

1601 Golden Aspen Drive, Suite 103
Ames, Iowa 50010
Phone: (515) 233-0000
FAX: (515) 233-0103

GROUNDWATER CONTOUR MAP OCTOBER 2007

MUSCATINE C & D LANDFILL MUSCATINE, IOWA

FIGURE	Ξ: 1	1	
REVISION	NO.	DATE	
DRAWN JAK	PROJECT NO. 6008-03B	DATE 11-26-07	

ATTACHMENT A

Permit & Amendments





STATE OF IOWA

CHESTER J. CULVER, GOVERNOR PATTY JUDGE, LT. GOVERNOR

DEPARTMENT OF NATURAL RESOURCES
RICHARD A. LEOPOLD. DIRECTOR

February 14, 2007

Lavene Payne, Solid Waste Manager City of Muscatine 1000 S Houser Muscatine, IA 52761

TOW -

RE: City of Muscatine C & D Landfill (CLOSED)
2006 Annual Water Quality Report
Permit No. 70-SDP-04-78C

Dear Mr. Payne:

We have reviewed the 2006 Annual Water Quality Report (AWQR), dated November 28, 2006, as submitted on your behalf by FOX Engineering Associates, Inc.

Based on our review of the report, the Department authorizes continued implementation of the recommended monitoring program, as follows:

1. Continued semiannual water quality analysis shall be conducted at all approved monitoring points as defined in the Special Provisions of the permit and/or any subsequent amendments.

All future AWQRs should include the 12 items described in the Department's December 1, 2004 correspondence.

If you have any questions, please contact me at (515) 281-8045.

Sincerely,

Michael B. "Mick Leat"

Environmental Engineer

Energy and Waste Management Bureau

ML\2006WaterQualityltrMuscatineC&D.doc

copy: Doug Luzbetak, P.E.

FOX Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103

Ames, IA 50010

DNR Field Office #6 Nina Koger, DNR Mick Leat, DNR

STATE OF IOWA

THOMAS J. VILSACK, GOVERNOR SALLY J. PEDERSON, LT. GOVERNOR DEPARTMENT OF NATURAL RESOURCES
JEFFREY R. VONK, DIRECTOR

February 14, 2006

Lavene Payne, Solid Waste Manager City of Muscatine 1000 S Houser Muscatine, IA 52761

RE: City of Muscatine C & D Landfill (CLOSED) 2005 Annual Water Quality Report Permit No. 70-SDP-04-78C

Dear Mr. Payne:

We have reviewed the 2005 Annual Water Quality Report (AWQR), dated November 25, 2005, as submitted on your behalf by FOX Engineering Associates, Inc.

Based on our review of the report, the Department authorizes continued implementation of the recommended monitoring program, as follows:

1. Continued semiannual water quality analysis shall be conducted at all approved monitoring points as defined in the Special Provisions of the permit and/or any subsequent amendments.

All future AWQRs should include the 12 items described in the Department's December 1, 2004 correspondence.

If you have any questions, please contact me at (515) 281-8045.

Sincerely,

Michael B. "Mick Leat"

Environmental Engineer

Energy and Waste Management Bureau

ML\2005WaterQualityltrMuscatineC&D.doc

copy: Leslie Wolfe, P.E.

FOX Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103 Ames, IA 50010 DNR Field Office #6 Nina Koger, DNR Mick Leat, DNR



RECEIVED DEC 0 6 2004

LSW Tand

STATE OF IOWA

Thomas J. Vilsack, governor ally J. Pederson, Lt. governor

DEPARTMENT OF NATURAL RESOURCES

JEFFREY R. VONK, DIRECTOR

DJL _

to a so our

December 1, 2004

Lavene Payne, Solid Waste Manager City of Muscatine 1000 S Houser Muscatine, IA 52761

RE: City of Muscatine C & D Landfill (CLOSED) 2004 Annual Water Quality Report Permit No. 70-SDP-04-78C

Dear Mr. Payne:

We have reviewed the 2004 Annual Water Quality Report (AWQR), dated November 23, 2004, as submitted on your behalf by FOX Engineering Associates, Inc.

Based on our review of the report, the Department authorizes continued implementation of the recommended monitoring program, as follows:

1. Continued semiannual water quality analysis shall be conducted at all approved monitoring points as defined in the Special Provisions of the permit and/or any subsequent amendments.

In addition, all future AWQRs should include the following, starting with November 30, 2005 report:

- 1. A brief history of the site that describes the geology, hydrogeology, previous land-use, and solid waste streams.
- 2. An 11"x17" scaled site map delineating the approved monitoring network. All groundwater and surface water monitoring points shall be conspicuously marked and show its function as an upgradient, background, or downgradient sampling location.
- 3. A groundwater table contour map to evaluate groundwater pathways and to evaluate potential groundwater mounding. Data from leachate piezometers or wells should be included on the groundwater table contour map.
- 4. A potentiometric map should be included if a confined unit is being monitored.
- 5. A discussion of potential groundwater mounding and its influence on upgradient and downgradient wells.
- 6. A table showing all current and historic water quality data.

- 7. An evaluation of all upgradient groundwater and surface water points to determine whether they are currently functioning as a valid background/upgradient sampling points based on the groundwater table contour map and water quality data results.
- 8. Control limit calculations for each upgradient or background groundwater sampling point and whether the corresponding downgradient monitoring point falls within the calculated limits.
- 9. Graphical representation of water quality data in readable form. The current control limits and, if applicable, the Maximum Contaminant Levels (MCLs) should be clearly shown on each graph.
- 10. A discussion of the water quality data results stating whether potential leachate migration is occurring beyond the waste boundary at any groundwater monitoring point. If MCLs are exceeded, provide information on potential receptors.
- 11. A discussion, as applicable, of the potential impact of the landfill on surface water quality.
- 12. Conclusions and recommendations for future monitoring.

If you have any questions, you may contact me at (515) 281-8968.

Sincerely,

Jeff Simmons

Environmental Engineer

Energy and Waste Management Bureau

MMW

JNS\JNS\J:2004WaterQualityltrMuscatineC&D.doc

copy: Veslie Wolfe, P.E.

FOX Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103

Ames, IA 50010

DNR Field Office #6

Nina Koger, DNR

Jeff Simmons, DNR



STATE OF IOWA

OMAS J. VILSACK, GOVERNOR SALLY J. PEDERSON, LT. GOVERNOR DEPARTMENT OF NATURAL RESOURCES
JEFFREY R. VONK, DIRECTOR

DJL Z

July 2, 2003

Lavene Payne, Solid Waste Manager
City of Muscatine
1000 S Houser
Muscatine, IA 52761

RE: City of Muscatine C & D Landfill (CLOSED)
Permit No. 70-SDP-04-78C
Amendment #3

Dear Mr. Payne:

Enclosed is Amendment #3 to the permit issued on December 29, 1994, for the City of Muscatine C & D Landfill (CLOSED). The amendment and approved plans must be kept with the permit and the approved plans at the sanitary disposal project in accordance with solid waste rule 567 IAC 114.26(2)"c". Please review this amendment with your operators, as they must become familiar with it.

In accordance with the February 20, 2003 request from FOX Engineering Associates, Inc., the enclosed amendment authorizes the permit holder to move the schedule of monitoring events one month earlier by 1) Allowing the semiannual sampling to be conducted in March and September of each year; 2) Allowing the annual sampling to be conducted in September of each year; and 3) Allowing the water level measurements to be conducted in March and September of each year.

Note that the amendment may contain conditions that require a response or action by you, which if not properly complied with, may prompt enforcement action by this department.

If you have any questions, you may contact me at 515/281-8968.

Sincerely,

Jeff Simmons

Environmental Engineer

Energy & Waste Management Bureau

JNS\JNS\J:MuscatineC&D94amd3X.doc

Attachments

cc:

Todd Whipple, C.P.G.

FOX Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103 Ames, IA 50010

DNR Field Office #6

Nina Koger, DNR

Jeff Simmons, DNR

IOWA DEPARTMENT OF NATURAL RESOURCES AMENDMENT #3

Issued by:

Nina M. Koger

Environmental Services Division

For: the Director

Date Issued:

July 2, 2003

Permit number 70-SDP-04-78C, issued on December 29, 1994, for the City of Muscatine C&D Landfill (CLOSED) is hereby amended by the following:

In accordance with the variance approval of September 15, 1998, the permit holder is authorized to reduce the frequency of groundwater level measurements from monthly, as required by current subrule 567 IAC 114.26(4)"b", to semiannually.

Accordingly, in accordance with the February 20, 2003 request from FOX Engineering Associates, Inc., the permit holder is authorized to conduct water quality sampling and water level measurements in March and September rather than April and October.

Replace Special Provision #5b and #5g with the following:

#5b. Quarterly sampling of the approved monitoring points has been completed. Continued semiannual sampling shall take place in March and September of each year for the parameters listed in 567 IAC 114.26(4)"e". Routine annual testing for the parameters listed in 567 IAC 114.26(4)"f" shall be conducted during September of each year.

The elevation of water in each monitoring well shall be measured and recorded on a semiannual basis in March and September.

#5g. An Annual Water Quality Report (AWQR) summarizing the effects the facility is having on groundwater and surface water quality shall be submitted to the Department's Main and local Field offices by November 30 each year. This report shall be prepared in accordance with 567 IAC 114.26(8)"d" by a Professional Engineer licensed in the State of Iowa. The AWQR shall include the results of the semiannual groundwater measurements and the routine semiannual and annual groundwater quality analyses conducted at the approved monitoring points. By means of a variance granted on September 15, 1998, groundwater measurements may be taken on a semiannual basis.

NMK\JNS\J: MuscatineC&D94amd3.doc



STATE OF IOWA

THOMAS J. VILSACK, GOVERNOR SALLY J. PEDERSON, LT. GOVERNOR

DEPARTMENT OF NATURAL RESOURCES
JEFFREY R. YONK, DIRECTOR

January 18, 2002

Robert McDonald, P.E. Assistant City Engineer Department of Public Works 1459 Washington Street Muscatine, IA 52761-5042

SUBJECT: City of Muscatine C&D Landfill

#70-SDP-4-78C

Dear Mr. McDonald:

This letter constitutes Amendment #2 to the permit issued December 29, 1994 for the City of Muscatine C&D Landfill. The amendment and approved plans must be kept with the permit and the approved plans at the sanitary disposal project in accordance with solid waste rule 103.2(2)'c', IAC. Please review this amendment with your operators, as they must become familiar with it.

The amendment adds the following as a Special Provision to your permit:

The Emergency Response and Remedial Action Plan (ERRAP) prepared by Fox Engineering Associates, Inc. that was received on December 28, 2001 is in compliance with 567 IAC 102.16 and is hereby approved. An updated ERRAP shall be submitted at the time of any significant changes in facility closure operations that require modification of the currently approved ERRAP.

If you have any questions regarding this amendment, please contact Nina M. Koger at (515) 281-8986.

Sincerely,

Lavoy Haage Supervisor

Solid Waste Section

Illad-16

LH:nmf

ATTACHMENT

cc: Field Office 6

N. Koger, IDNR

F. Hallada, IDNR

A.J. Johnson, City Administrator City Hall Muscatine, IA 52761

Lavene Payne, Solid Waste Manager Public Works Bldg. 1459 Washington Street Muscatine, IA 52761

Fox Engineering 1601 Golden Aspen Drive, Suite 103 Ames, IA 50010 TERRY E. BRANSTAD, GOVERNOR

DEPARTMENT OF NATURAL RESOURCES
LARRY J. WILSON, DIRECTOR

September 15, 1998

Robert McDonald, P.E. Assistant City Engineer Department of Public Works 1459 Washington Street Muscatine, IA 52761-5042

SUBJECT: Muscatine County Sanitary Landfill

#70-SDP-4-78C C+D landfill

Dear Mr. McDonald:

Enclosed is Amendment #1 to the permit issued December 29, 1994 for the Muscatine County Sanitary Landfill. The amendment must be kept with the permit and the approved plans at the sanitary disposal project in accordance with solid waste rule 103.2(2)'c', IAC. Please review this amendment with your operators, as they must become familiar with it.

The enclosed amendment (1) authorizes a reduction in the frequency of water level measurements from a monthly basis to a semiannual basis; (2) authorizes the permit holder to cease methane gas monitoring and annual reporting; and (3) authorizes a reduction in the frequency of routine site inspections from a monthly basis to a semiannual basis.

Please note that the permit contains special provisions that may require a response or action by you which, if not properly complied with, may prompt enforcement action.

If you have any questions regarding this amendment, please contact Nina M. Koger at (515) 281-8986.

Sincerely,

Lavoy Haage Supervisor

Solid Waste Section

LH:nmf

ATTACHMENT

.cc: Field Office 6

- N. Koger, IDNR
- F. Hallada, IDNR

A.J. Johnson, City Administrator 'Çity Hall Muscatine, IA 52761

Lavene Payne, Solid Waste Manager Public Works Bldg. 1459 Washington Street Muscatine, IA 52761

Fox Engineering 1531 Airport Road Ames, IA 50010 IOWA DEPARTMENT OF NATURAL RESOURCES

AMENDMENT #1

Issued by:

F. Hallada, P.E.

Environmental Protection Division

HALLADA

For: the Director

Date Issued: September 15, 1998

Permit number 70-SDP-4-78C for the Muscatine C&D Sanitary Landfill is hereby amended by the following:

- 1. In accordance with the variance approval of September 15, 1998, the permit holder is authorized to reduce the frequency of groundwater level measurements from monthly, as required by subrule 103.2(4)b IAC, to semiannually. The measurements shall be taken in April and October of each year, with the results submitted in the corresponding semiannual monitoring reports.
- 2. In accordance with the variance approval of September 15, 1998, the permit holder is authorized to cease methane gas monitoring and annual reporting, as required by IAC Subrule 103.2(15). However, in the event that methane gas is found to be present at the site, gas monitoring shall be immediately implemented.
- 3. The permit holder is authorized to reduce the frequency of routine site inspections from monthly, as required by Special Provision #6 of the permit, to semiannually. The inspections shall be conducted in April and October of each year, with the results submitted in the corresponding semiannual engineering inspection reports.



RRY E. BRANSTAD, GOVERNOR

DEPARTMENT OF NATURAL RESOURCES LARRY J. WILSON, DIRECTOR

December 29, 1994

Lavene Payne, Solid Waste Manager Department of Public Works 1459 Washington Street Muscatine, IA 52761-5042

Re: · City of Muscatine C&D Landfill

#70-SDP-4-78C

Dear Mr. Payne:

Enclosed is the closure permit for the City of Muscatine Construction and Demolition Sanitary Landfill. The permit and the approved plans must be kept on file for post closure use and reference. Please review the closure permit and plans with your staff, as they must become familiar with them.

Please note that the permit contains special provisions that may require a response or action by you which, if not properly complied with, may prompt enforcement action.

The permit is authorized continued use of the area as construction rubble fill site.

If you have any questions regarding this permit, please contact Nina M. Koger at (515) 281-8986.

Sincerely,

Lavoy Haage

Supervisor

Solid Waste Section

LH: nmf

ATTACHMENT

Field Office 6 CC:

N. Koger, IDNR

F. Hallada, IDNR

A.J. Johnson, City Administrator City Hall Muscatine, IA 52761

Mr. Robert McDonald, P.E. Public Works Bldg. 1459 Washington Street Muscatine, IA 52761

Jim Mikolaitis, P.E. GES, Inc. P.O. Box 9007 Cedar Rapids, IA 52409-9007

IOWA DEPARTMENT OF NATURAL RESOURCES SANITARY DISPOSAL PROJECT PERMIT

I. Permit Number: 70-SDP-4-78C

II. Permitted Agency: City of Muscatine

III. Project Location: Part of the NE 1/4, Sec. 3, T76N,

R2W, 3 Acres, Muscatine County, Iowa

IV. Responsible Official

Name: Lavene Payne, Solid Waste Manager

Address: Department of Public Works

1459 Washington Street Muscatine, IA 52761-5042

Phone: 319/263-8933

V. Registered Design Engineer

Name: Jim Mikolaitis, P.E. Address: Howard R. Green Company

P.O. Box 9007

Cedar Rapids, IA 52409-9007

Phone: 319/395-0578

Registration Number: 11949

VI. Date Permit Issued: December 29, 1994

VII. Permit Expiration Date: December 29, 2024

VIII. Issued by: Environmental Protection Division

for the Director

IX. General Provisions

The above named permitted agency is hereby authorized to close the sanitary landfill at the described location in conformance with Chapter 455B of the Code, the rules pursuant thereto existing the time of issuance, and any subsequent new rules which may be duly adopted, and any provisions contained in Section X of this permit.

The facility shall be closed according to the engineering plans and specifications approved by the Department of Natural Resources and these shall become a part of this permit. Any modifications or deviations from the engineering plans and specifications must have prior approval by the Department and an amendment to this permit issued.

The issuance of this permit in no way relieves the applicant of the responsibility for complying with all other local, state, and federal statutes, ordinances, and rules or other requirements applicable to the closure and maintenance of this closed sanitary landfill.

No legal or financial responsibility arising from the closure and post closure of the approved project shall attach to the state of Iowa or the Department of Natural Resources due to the issuance of this permit.

If title to this project is transferred, the new owner must apply to the Department for a transfer of this permit within thirty days of the date of title transfer. This transfer is void sixty days after the date of title conveyance unless the Department has transferred the permit.

This facility shall be surveyed as necessary and inspected as described in the special provisions of this permit. Semiannual reports shall be prepared containing a brief report describing the site's conformance and nonconformance with the permit and the approved plans and specifications during the inspections. These reports shall be submitted by May 1 and November 1 each year to both the Field and Main offices of the Department. The Department shall be notified if any inspection reveals any nonconformance with the permit and approved plans and specifications.

Failure to comply with Chapter 455B of the Code, or any rule of order promulgated pursuant thereto, or any or all provisions of this permit may result in a civil penalty of up to \$5000 for each day of violation, pursuant to Section 455B.307 of the Code.

X. Special Provisions

- 1. The thirty-year post closure period for this facility begins on the date of issuance of this Closure Permit.
- 2. This site shall be closed and maintained in accordance with the approved Construction and Demolition Debris/Construction Rubble Landfill Closure and Post Closure Plan (C/PCP), dated May 2, 1994, and Plans dated March 19, 1994, as submitted by Green Environmental Services, Inc. (GES).
- 3. Issuance of this closure permit prohibits any additional regulated waste disposal, recycling, composting, and other related landfill activities which are subject to permit approval. However, the permit holder is

authorized continued use of the closed landfill for construction rubble fill, in accordance with the approved documents and permit conditions.

- The permit holder shall submit a closure compliance report certified by a professional engineer registered in 4. the State of Iowa upon completion of the final cap placement. The report shall certify that the site closure has been implemented in compliance with the rules, the Closure and Post Closure Plan, and the permit. The following information must be included in the report:
 - As built plans showing changes from approved design plans, including the grading and seeding of borrow areas.
 - b. A copy of the notation filed with the county recorder showing, for the purposes of title abstract, the existence of a landfill on the property, the types of wastes disposed of and dates of landfill use.
- This site shall be monitored for water quality in 5. accordance with the approved Hydrogeologic Investigation Report and Hydrologic Monitoring System Plan (HMSP), dated February 28, 1994, as submitted by GES.
 - The HMSP shall include groundwater monitoring points MW-2, MW-3, MW-4, MW-6, and MW-7

In addition, monitoring points MW-1, MW-5, and PZ-8 shall be retained as water level measuring points.

- b. First year quarterly sampling shall begin in April 1995. Subsequent quarterly sampling shall continue in July and October 1995, and January 1996 for analysis of the parameters listed in subrule 103.2(4)d and e IAC. Continued semiannual sampling shall take place in April and October of each year for the parameters listed in subrule 103.2(4)e IAC, beginning in April 1996. Routine annual testing for the parameters listed in subrule 103.2(4)f shall be conducted during October of each year, beginning in October 1995.
- Samples collected for dissolved metals analysis shall be field filtered, preserved, and promptly transferred to a certified laboratory.
- The Method Detection Limit (MDL) for the test d. parameters shall not exceed action levels as defined under IAC Chapter 133. If the action levels cannot be feasibly achieved using procedures described in

IAC Subrule 103.2(5), then the MDL shall not exceed the lowest feasible level.

- If laboratory test results exceed the upgradient e. mean plus two standard deviations or the Maximum Contaminant Level (MCL) for any parameter, the Department shall be notified within 30 days of receipt of the analytical results.
- f. Results of all analysis and the associated sampling forms shall be submitted to both the field and main offices of this department within 45 days of the sample collection.
- annual report summarizing the effects facility is having on groundwater and surface water quality shall be submitted to the Department by November 30 of each year. This report shall be prepared in accordance with IAC Subrule 103.2(8)d by a professional engineer registered in the state of Iowa. This report shall include the results of groundwater level measurements conducted in the monitoring wells.
- 6. This site shall be inspected monthly for the first year, or more frequently depending on weather conditions. The frequency of routine inspections may be decreased, after the first year, but no less frequent than semiannually, if the permit holder provides justification that monthly inspections are no longer necessary to ensure proper maintenance of the site. Summarize all inspection data in the semiannual report defined in the General Provisions.
- All diversion and drainage systems must be maintained to the approved specifications to prevent run-on and runoff erosion, or other damage to the final cover. These diversion and drainage structures must be designed to meet a 25-year, 24 hour rainfall event.
- 8. The vegetative cover shall be reseeded as necessary to maintain good vegetative growth. Any invading vegetation whose root system could damage the compacted soil layer shall be removed or destroyed immediately.
- 9. The integrity and effectiveness of the final cover must be maintained by making repairs as necessary to correct the effects of settling, subsidence, erosion, or other events. If damage to the final cover compacted soil layer occurs, repairs shall be made to correct the damage and return it to original specifications.
- 10. The permit holder shall quarterly monitor and annually report site methane concentrations in accordance with subrule 103.2(15) IAC after May 18, 1994. Specific

actions, as defined in the rules, shall be taken in the event of methane gas level limit exceedances The annual report summarizing the methane gas monitoring results and any action taken resulting from gas levels exceeding the specified limits during the previous 12 months shall be submitted by November 30 of each year.

- 11. The permit holder is conditionally exempt from providing and implementing a leachate control system plan. Continued exemption is subject to compliance with water quality standards, statistical limits per IAC subrule 103.2(6) through 103.2(8), and the control of leachate at the site. In the event that these conditions are violated, the permit holder shall be required to submit a groundwater quality assessment plan in accordance with IAC subrule 103.2(9).
- The permit holder is exempt from Financial Assurance requirements, as provided in IAC Chapter 111, since municipal solid waste has not been disposed of at this facility.

ATTACHMENT B

Hydrogeologic Investigation Report & Hydrologic Monitoring System Plan




FIGURE 1

SITE LOCATION MAP

CONSTRUCTION RUBBLE LANDFILL

MUSCATINE, IOWA FEBRUARY, 1994







FIGURE 4

FEBRUARY, 1994



CONSTRUCTION RUBBLE LANDFILL MUSCATINE, IOWA

FEBRUARY, 1994

TABLE 2. WATER LEVEL DEPTHS AND ELEVATIONS

DEPTHS, IN FEET, MEASURED FROM TOP OF CASING Ä

WELL # 11/4/93 1 MW-3 7.08	11/23/93 7.24	12/9/93 7.53	12/16/93 7.62	1/20/94 8.46
	6.05	6.10	7.71	6.40
	5.60	5,64	6.22	5.97
-	70 97	47.00	11 40	1000
	10.94	02.11	D4. / -	00.01
	16.72	17.15	17.70	18.50
	48.94	40.76	41.05	41.75
	57.04	53,54	52.57	50.95
	42.30			42.26

B. WATER LEVEL ELEVATIONS, IN FEET MSL.

WELL #	TOC Elev.	11/4/93	11/23/93	12/9/93	12/16/93	1/20/94
MW-3	640.36	633.28	633.12	632.83	632.74	631.90
MW-2	640.86	634.62	634.81	634.76	633.15	634.46
MW-1	640.42	573.78	634.82	634.78	634.20	634.45
MW-4	693.22	87.979	676.28	676.02	675.73	675.17
		-				
MW-7	716.65	700.30	699.93	699.50	698.95	698,15.
MW-6	716.63	677.25	69'.299	675.87	675.58	674.88
MW-5	716.80	646.05	659.76	663.26	664.23	665.85
LPZ-8	692.99	650.94	69'059	•	1	650.73




FIGURE 6

WATER TABLE CONTOUR MAP CONSTRUCTION RUBBLE LANDFILL

MUSCATINE, IOWA FEBRUARY, 1994



Hydraulic Properties

1. Hydraulic gradients are presented in Table 3. Horizontal gradients were obtained from the potentiometric map of the water table (Figure 6). Horizontal hydraulic gradients measure the steepness of the water table. These gradients vary from 0.122 to 0.299. Directions converge toward the ravine.

Vertical hydraulic gradients are also presented in Table 3. Head differences were calculated for shallow to mid-level and mid-level to deep wells in the triple clusters, with the exception of the gradient between MW-6 and MW-7. There is a discontinuity in the saturated zone within the sand screened by MW-6, which prevents calculation of a vertical gradient for this well pair. The overall gradient was calculated between MW-1 and MW-3. Vertical gradients varied from 0.0 to 0.351. The direction is downward for the upgradient cluster.

On January 20, 1994, the water levels in MW-1 and MW-2 varied by 0.01 feet, which is within the limit of measurement of + or - 0.01 feet. Thus, there was no tendency for vertical movement between these two wells. However, both wells had a higher water level than MW-3, the shallow well. Thus, there was an upward gradient for each well compared to MW-3, as portrayed on Figure 5. Vertical gradients for December 16, 1993 are also presented. On that date, the typical upward gradient between MW-1 and MW-2 was present.

The numerical values of hydraulic gradients are important for use in calculations. However, to visualize the three-dimensional flow pattern, it is better to refer to the cross sections and map in Figures 4 through 6.

2. Laboratory hydraulic conductivities (permeabilities) are presented in Table 4 and Appendix F. These were determined by means of a constant head test on an undisturbed sample. The samples for laboratory tests were taken from a cohesive sediment below the depth of waste disposal except for MW-4, where no suitable

CONSTRUCTION RUBBLE LANDFILL MUSCATINE, IOWA

FEBRUARY, 1994

TABLE 3. HYDRAULIC GRADIENTS

A. HORIZONTAL HYDRAULIC GRADIENTS (1,)

WELL NUMBER	i, on 1/20/94	DIRECTION
MM-3	0.259	Southeast
FX-4	0.191	Southeast
T=ZZ	0.122	South Southeast
LPZ-8	0.299	South

B. VERTICAL HYDRAULIC GRADIENTS (1,)

WELL PAIRS	1, on 12/16/93	DIRECTION	i, on 1/20/94	DIRECTION
MW-2 to MW-3	0.021	Upward	0.131	Upward
MW-1 to MW-2	0.038	Upward	0.000	Horizontal
MW-1 to MW-3	0.031	Upward	0.054	Upward
MW-6 to MW-5	0.351	Downward	0.285	Downward

CONSTRUCTION RUBBLE LANDFILL MUSCATINE, IOWA

FEBRUARY, 1994

TABLE 4. HYDRAULIC CONDUCTIVITIES (K)

A. LABORATORY HYDRAULIC CONDUCTIVITIES (Measured by a constant head test on an undisturbed sample)

WELL NO.	DEPTH IN FEET	K in cm/s	SEDIMENT TYPE
MW-1	62-63	1.8 x 10 ⁻⁸	Till
MW-5	33-34	3.0 x 10 ⁻⁹	Till
LPZ-8	45-46	4.4 x 10 ⁻⁹	Till

B. IN-SITU HYDRAULIC CONDUCTIVITIES (Measured by a bail test)

WELL NO.	SCREEN DEPTH IN FEET	K in cm/s	SEDIMENT TYPE
MW-3	10-20	3.7 x 10 ⁻³	Alluvial Silt and Sand
MW-2	30-40	1.6 x 10 ⁻⁴	Intratill Sand Lens
MW-1	60-65	2.0 x 10 ⁻⁵	Intratill Sand Lens
MW-4	12.5-22.5	1.5 x 10 ⁻³	Eolian Sand
MW-7	10-20	1.3 x 10 ⁻³	Eolian Sand
MW-6	37-47	5.8 x 10 ⁻⁵	Intratill Sand Lens
MW-5 .	69-74	3.1 x 10 ⁻⁸	Till

sample was available. Values varied from 3.0×10^{-9} to 1.8×10^{-8} centimeters per second (cm/s). All samples were till. These values indicate a very low permeability.

In-situ hydraulic conductivities were determined by means of bail tests. The results are presented in Table 4 and Appendix F, along with a description of the saturated and/or most permeable sediment in the screened interval. Where small, isolated sand lenses are surrounded by till, groundwater movement depends on the conductivity of the till and the surface area of the contact between sand and till as well as the conductivity of the sand. When wells are screened across both sand and till, the measured value is intermediate between the conductivity of the sand and till.

Hydraulic conductivities for intratill sand lenses varied from 2.0 \times 10⁻⁵ to 1.6 \times 10⁻⁴ cm/s. The conductivities for eolian sand were 1.3 \times 10⁻³ and 1.5 \times 10⁻³ cm/s. The conductivity for alluvial silt over sand was 3.7 \times 10⁻³ cm/s.

A bail test run for 110 minutes on MW-5 resulted in a hydraulic conductivity of 1.6 X 10⁻⁵ cm/s, which appeared to be too high for a well which needed 2.5 months to stabilize or nearly stabilize. The continuous samples from the borehole were clay-rich till throughout the screened interval. Therefore, five water level measurements taken over this time period were analyzed to obtain a hydraulic conductivity of 3.1 X 10⁻⁸ cm/s. According to LaDon Jones of Iowa State University (personal communication), this is a valid procedure after the well has stabilized. The difference in results is due to the effect of the developed zone around the well during the relatively short bail test procedure (Bouwer, 1989) (Jones, 1993). If the bail test had been extended to 24 or 48 hours, similar results would have been obtained.

This low <u>in-situ</u> hydraulic conductivity of 3.1 X 10⁻⁸ cm/s for the glacial till demonstrates that the till will prevent downward flow into the bedrock aquifer. The till below a depth of 65 feet in the boring for MW-1 is likely to have an even lower permeability because it was too dense to drill with hollow stem augers and required rotary drilling.

A common form of Darcy's Law is Q = K*i*A, where Q is the flow rate, K is <u>3.</u> the hydraulic conductivity, i is the hydraulic gradient, and A is the cross sectional area of inflow (Freeze and Cherry, 1979). Horizontal and vertical flow rates for one square foot of area are presented in Table 5. The horizontal flow rates were calculated using the horizontal gradients and in-situ hydraulic conductivities for the water table wells. The vertical flow rates for MW-5 and MW-6 were calculated using the vertical gradient and the lower in-situ hydraulic conductivity for each pair. The lower conductivity is used because sediments with lower conductivity will restrict the groundwater flow. However, the true flow rates may be less than calculated for the cluster including MW-1, MW-2, and MW-3, since the hydraulic conductivities of the intervening till units are No vertical hydraulic gradient nor vertical flow rate was calculated unknown. for MW-6 and MW-7 due to the discontinuity of the saturated zone where part of the sand lens is dry (unsaturated) within the screened interval of MW-6.

The horizontal flow rates vary from 0.882 to 5.358 f^3/d . Upward flow rates between MW-2 and MW-3 were 0.019 and 0.120 on two separate days. The upward flow rates between MW-1 and MW-2 were 0.0 and 0.004. The vertical flow rates, directed downward, at MW-5 and MW-6 are 2.5 X 10^{-5} and 3.1 X 10^{-5} f^3/d . The vertical flow rates are less than the horizontal. Vertical flow rates decrease with depth. Thus, there is a strong tendency for the groundwater to flow laterally in the shallow sediments.

CONSTRUCTION RUBBLE LANDFILL MUSCATINE, IOWA

FEBRUARY, 1994

TABLE 5. GROUNDWATER FLOW RATES AND TRANSMISSIVITIES

A. HORIZONTAL FLOW RATES (Q_h)

WELL NO.	Q _n on 1/20/94 in f ³ /d	DIRECTION
MW-3	5.358	Southeast
MW-4	1.630	Southeast
MW-7	0.882	South Southeast

B. VERTICAL FLOW RATES (Q,)

WELL PAIR	Q on 12/16/93 in f³/d	DIRECTION	Q on 1/20/94 in f³/d	DIRECTION
MW-2 to MW-3	0.019	Upward	0.120	Upward
MW-1 to MW-2	0.004	Upward	0.000	Horizontal
MW-6 to MW-5	3.1 X 10 ⁻⁵	Downward	2.5 X 10 ⁻⁵	Downward

C. TRANSMISSIVITIES (T)

WELL NO.	AQUIFER THICKNESS IN FEET	T in f²/d	SEDIMENT TYPE					
MW-3	11.5	237.9	Alluvial Silt and Sand					
MW-2	10	9.16	Intratill Sand Lens					
MW-1	2	0.23	Intratill Sand Lens					
MW-4	9	76.8	Eolian Sand					
MW-7	12.5	90.35	Eolian Sand					
MW-6	4.5	1.47	Intratill Sand Lens					
MW-5	8*	0.0007	Till					
* Length of sandpack								

- Transmissivity is defined as the hydraulic conductivity multiplied by the <u>4.</u> aquifer thickness. For unconfined aquifers, only the saturated thickness is Transmissivities are often reported for aquitards, however, the hydraulic conductivity has more significance. The transmissivities have been calculated using in-situ hydraulic conductivities. The highest transmissivity, for alluvium, is 237.9 f^2/d (Table 5). The transmissivities for eolian sand are 76.8 and 90.35 f_2/d . Transmissivities for intratill sand lenses vary from 0.23 The transmissivity for deep till is $0.0007 f^2/d$. to 9.16 f^2/d . transmissivities show a progression from higher transmissivities for shallow to lower transmissivities for deep sediments varying over 6 orders of magnitude. According to Driscoll (1986), a good aquifer for domestic use should have a transmissivity greater than $1400 \, f^2/d$, and an aquifer used for a municipal water supply, industry, or irrigation should have a transmissivity greater than 14,000 f^2/d . None of the sediments at the landfill site would be suitable as a water supply aquifer, even for domestic purposes.
- 5. Storage coefficient or specific yield can only be determined from wells where pumping tests can be conducted (Freeze and Cherry, 1979). This would involve pumping one well and noting drawdown in other wells screened in the same aquifer. No such data are available for the landfill site.

Designation of Aquitards and Aquifers

Groundwater flow lines and equipotential lines are refracted at a geologic contact where the hydraulic conductivities vary (Freeze and Cherry, 1979). Flow tends to be nearly horizontal in materials with high conductivity and nearly vertical in materials with low conductivity. The larger volume of water would flow laterally in the material with larger conductivity and a smaller volume would move vertically through the material with a low conductivity. This

information, derived from consideration of groundwater flow theory, along with the hydraulic properties calculated for sediments at the landfill, allow designation of aquifers and aquitards.

The deeper part of the glacial till is an aquitard. This is shown by the low <u>in-situ</u> hydraulic conductivity, flow rate, and transmissivity measured at MW-5 and the nearly vertical flow paths at MW-5 and MW-6. The need to use rotary drilling below 65 feet at MW-1 suggests high density and low conductivity for the deep till at that location.

The eolian sand at MW-4 and MW-7 and the alluvial sequence at MW-3 are. aquifers, as shown by the higher hydraulic conductivities, flow rates, and transmissivities. The shallow till with sand seams and lenses encountered at B-1 and MW-1 at shallow depths has an intermediate hydraulic conductivity, flow rate, and transmissivity. It is likely that the shallow till, with or without sand lenses, functions as an aquifer compared to the deep till. At many other sites, shallow weathered till has a conductivity on the order of 10-6 cm/s. The yellow brown color of the shallow till at the MW-5 location and at LPZ-8 is a symptom of weathering. The shallow till at the MW-1 location had sand fracture fills, which indicates weathering, but the constant saturated condition below the ravine prevented formation of the yellow brown color. Shallow weathered till likely extends below the entire ravine under the eolian sand and alluvium. contaminated groundwater moving out of the waste would move laterally through the alluvium and weathered till. The eolian sand, alluvium, and weathered till with or without sand lenses form the uppermost aquifer. The water table is situated Water Table and within this aquifer.__

Nater lable and Uffermost Aquifer are same unit.

Conclusions of the Investigation

- 1. Horizontal flow paths converge toward the ravine.
- 2. Vertical flow paths in the till are downward upgradient from the landfill, nearly horizontal at midslope, then upward toward the base of the ravine.
- 3. The eolian sand, alluvium, and upper till form the uppermost aquifer. The deep till functions as an aquitard.
- 4. The water table is situated in the uppermost aquifer.
- 5. There are no intermittent streams nor permanent streams on the landfill property, though the drainage way in the ravine downhill from the landfill would contain flowing water after heavy precipitation or snowmelt.

HMSP PROPOSAL

PART IV

HYDROLOGIC MONITORING SYSTEM PLAN

Introduction

In light of the conclusions of the investigation, no surface water monitoring is needed, and the following wells should be monitored: MW-2, MW-3, MW-4, MW-6, and MW-7. Wells MW-1 and MW-5 will be used as water level measuring points. The letter of October 15, 1993 from IDNR provided a waiver to the minimum requirement of three downgradient water table wells due to the small size of the landfill and severe access restrictions. An evaluation of each monitoring well is provided below.

Locations of Monitoring Wells

MW-1. This well is screened from 60 to 65 feet, across a 2-foot sand lens in the deep till aquitard. It will not be monitored, but will be used as a water level monitoring point.

MW-2. This well is screened from 30 to 40 feet across a 10-foot intratill sand lens. It is downgradient. The material between this sand lens and the overlying alluvium is as follows: There are 1.5 feet of till with sand fracture fill immediately below the alluvium, 5 feet of till with no sand seams, and 5 feet of till with sand seams. The till is likely to be weathered, and the sand seams could interconnect away from the borehole. Therefore, this well should be monitored as an uppermost aquifer well.

MW-3. This well is screened from 10 to 20 feet in alluvium, which includes silt over 1.5 feet of sand. The silty alluvium forms the base of the waste-filled ravine. This is also a downgradient uppermost aquifer and water table well, toward which the shallow groundwater flow converges. It will be monitored.

MW-4. This well was drilled through 6.5 feet of waste near the west boundary of the waste. It is screened from 12.5 to 22.5 in very silty eolian sand and non-silty eolian sand. It is an uppermost aquifer and water table well that is downgradient from the northwest portion of the landfill. It will be monitored.

MW-5. This well is screened from 69 to 74 feet in the deep till aquitard. It will not be monitored, but will be used as a water level measuring point.

MW-6. This well is screened in from 37 to 47 feet across a 7-foot intratill sand lens and 3 feet of till. It is possible that this sand unit could be continuous to the waste boundary. Therefore, this well should be monitored as an uppermost aquifer well. It is in an upgradient position but if it is continuous with the waste, it could be downgradient, depending on the hydraulic head of the saturated zone within the waste. Even though it is likely to be upgradient, it should not be used as a baseline well for purposes of statistical analysis of monitoring results.

MW-7. This wells is screened from 10 to 20 feet in very silty eolian sand and non-silty eolian sand. It is an upgradient uppermost aquifer and water table well. It will be monitored and used as the baseline well for statistical purposes.

Operational Plan For The Monitoring System

Chemical Parameters

During the first year of operation of the hydrologic monitoring system, samples will be collected quarterly from each monitoring well. Samples will be analyzed for the lists of parameters in 103.2(4) "d" and "e", to be called "list d" and "list e" below.

After the first year, samples will be collected semiannually and analyzed for the parameters listed in 103.2(4) "e".

An annual water-quality report will be submitted to IDNR with the semi-annual engineering inspection report, by November 30 of each year, after the quarterly sampling is complete. The water quality report will summarize the effect the facility is having on groundwater quality. The report will discuss any changes or maintenance that are needed for the monitoring system. The report will include graphs for all chemical parameter concentrations versus time for each well. The control limits will be shown on the graphs. Results of activities and tests required by the well maintenance and reevaluation plan will be submitted with the report.

Sampling Protocol

A document titled "Procedure for Groundwater and Surface Water Sampling, Green Environmental Services, Inc., Cedar Rapids, Iowa, March, 1994" is included in Appendix G. An addendum to this standard protocol, as requested by Rob McDonald of the City of Muscatine on March 23, 1994, is presented in Appendix H. These documents discuss procedures to be used when sampling of monitoring wells is done at the City of Muscatine Construction Rubble Landfill. Duplicate and replicate samples and equipment blanks will not be analyzed unless required by IDNR, according to 103.2(7) I.A.C. If these are required, then procedures described in the protocol will be followed. MW-7 is upgradient and must be sampled first. The other wells should be sampled in the following order: MW-6, MW-2, MW-3. Water levels will be measured in wells when samples are collected.

dragie Domi

MARRENDIX.C

Leges and documentation forms for mws-throughemvez:secociforeerzs


MONITORING WELL / PIEZOMETER CONSTRUCTION DOCUMENTATION FORM

Disposal site name City of Muscatine C Well or Piezometer # MW-1 Date st	& D Landfill Permit <u>₹ 70</u> -SDP-4- 78 Parted 10/25/93 Date completed 10/27/93
A. Surveyed Locations and Elevations	
Locations (± 0.5 ft.):	Well Installation, continued:
Specify corner of site Survey grid	Till ton mode.
Distance and direction	Filter pack: Material Muscatine #0-C sand
along boundary 7028.2 N	Grain size Effective size = 0.930 mm
ali dinantian	Volume 3.0 c.f.
Distance and direction	Seal (minimum 3 ft. length above
from boundary to well 10480.6 E	filter pack):
	Material Bentonite grout
Elevations (±0.01 ft. MSL):	Placement method Tremied
Ground surface 638.70	Volume 21.8 c.f.
* Top of protective casing 640.41	
mon of well casing 640.42	Backfill (if different from seal):
Top of well casing 640.42 Benchmark elevation 723.29	Material Same as seal
Benchmark descriptionArrowhead bolt	Placement Method
at hydrant at Newell & Kindler Sts.	Volume
*Measured at hinge line	
B. Soil Boring Information	Surface seal design:
	Material of protective casing:
Name and address of construction	4" square steel set in concrete
company Aquadrill, Inc.	Material of grout between protective
R.R. 2, Box 18	casing and well casing:
Iowa City, IA 52240	Bentonite
Name of driller Jeff Joslyn	Protective cap:
Drilling methodHSA to 65 Rotary to 100	Material Steel (not airtight)
Drilling fluid Drilling mud for rotary	Vented? Y/N Locking? Y/N_Y
Bore hole diameter9" to 65, 4" to 100	Well cap:
Soil sampling method **	Material PVC expandable, not
Depth of boring 100.0'	Vented? Y/N tightened
** Laskey continuous sampler	D. Groundwater Measurement
C. Monitoring Well Installation	D. Gloundwater measurement
Casing material Schedule 40 PVC	Water level (± 0.01 ft. below top of
Length of casing 61.72'	inner well casing) 634,45 on 1/20/94
Outside casing diameter 2.375"	Stabilization time <1 month
Inside casing diameter 2.0"	Well development method Pneumatic
Casing joint type Flush threaded	bailer, used until water is clear
casing/screen joint typeFlush threaded	
Screen material Schedule 40 PVC	Upgradient or downgradient well?
Screen opening size 0.010" = 0.25 mm	(see piezometric map from Hydrogeo-
Screen length 5.0'	logic study) <u>Downgradient</u>
Depth of well 67.09'	Average depth of frostline 30"
Attachments: Driller's log. Pipe sche	edules and grouting schedules. showing location of all monitoring well
8 I/2 Inch x II Inch map	Difference of all monitoring well

and piezometers.

Form #542-127

ELEVATIONS: 1 0.01 FT. MSL DEPTHS: 1 0.1 FT. FROM GROUND SERFACE




field boring log Project Museraline CY/)	PAGE # 2 012
Boring No. 411 — Date Started 10-25-93 Date Co	
subsurface stratigraphy	water levels
,	While Drilling
From To Description TO Brey Hed-Coarse Sand Gravel 420 Grey & Clay W/SAVD & Gravel Till	O Hours A.B.
	well details Stick-up Cover Flush Cover
0 65.0 414 H.S. Auger 65.0 100.0 Much Rotary W41/8" Tri-Cove	Ø Grada III
Bottom of Boring 100.0	See Memorial
sample data	
Depth Number/Type Depth Number/Type	
CS = Continuous Sampler AS = Auger Sample	aguadril

MONIT ING WELL / PIEZOMETER CON RUCTION DOCUMENTATION FORM

A. <u>Surveyed Locations and Elevations</u>	
Locations (± 0.5 ft.): Specify corner of site Survey grid	Well Installation, continued:
Distance and direction	Filter pack:
along boundary 7023.3 N	Material Muscatine #0-C sand
	Grain size <u>Effective size = 0.930 m</u>
Distance and direction	Volume 5.3 c.f.
from boundary to well 10484.3 E	Seal (minimum 3 ft. length above
	filter pack):
	Material Bentonite grout
Elevations (±0.01 ft. MSL):	Placement method Tremied
Ground surface 638.70 * Top of protective casing 640.89	Volume 9.5 c.f.
* Top of protective casing 640.89	Backfill (if different from seal):
Top of well casing 640.86 Benchmark elevation 723.29	Material Same as seal
Benchmark elevation 723.29	Placement Method
Benchmark description Arrowhead bolt at hydrant at Newell & Kindler Sts.	Volume
*Measured at hinge line	7 O T CEMO
B. soil Boring Information	Surface seal design:
B. BOIL BOILING INTOIMABLE	Material of protective casing:
Name and address of construction	4" square steel set in concrete
company Aquadrill, Inc.	Material of grout between protective
R.R. 2, Box 18	casing and well casing:
Iowa City, IA 52240	Bentonite
Name of driller Jeff Joslyn	Protective cap:
Orilling method Hollow stem auger	Material Steel (not airtight)
Drilling fluid None	Vented? Y/N Locking? Y/N_Y_
Bore hole diameter 9"	Well cap:
Soil sampling method **	Material PVC expandable, not
Depth of boring 41.0'	Vented? Y/N tightened
** Laskey continuous sampler	D. Groundwater Measurement
C. Monitoring Well Installation	D. GIOUNGWALEL MEASUREMENT
Casing material Schedule 40 PVC	Water level (± 0.01 ft. below top of
Length of casing 32,16'	inner well casing) 634.46 on 1/20/9
Outside casing diameter 2.375"	Stabilization time <1 week
Inside casing diameter 2.0"	Well development method Pneumatic
Casing joint type Flush threaded	bailer, used until water is clear
Casing/screen joint typeFlush threaded	
Screen material Schedule 40 PVC	Upgradient or downgradient well?
Screen opening size 0.010" = 0.25 mm	(see piezometric map from Hydrogeo-
Screen length 10.0'	logic study) <u>Downgradient</u>
Depth of well 40.95'	Average depth of frostline 30"
**	
	·
nellanta prillanta las Dina sah	dules and grouting schodules
Attachments: Driller's log. Pipe sch	edules and grouting schedules.
8 1/2 inch X 11 inch man	showing location of all monitoring wel

Form #542-12:

ELEVATIONS: 1 0.01 FT. MSL DEPTHS: 1 0.1 FT. FROM GROUND SERFACE




Field boring log Project Muscative C+D LANGTICE Boring No. MW-2 Date Started 10-27-53 Date Co Drilled by Ay + Traylogged by Ay Rig Of	
subsurface stratigraphy	water levels
04" Flight Augers 24%" ID H.S. 06%" ID H.S.	While Drilling
From To Description See HW-1 For Soils log	O Hours A.B.
0 7.0 Hard Stilling Brist Courtek	Well details Destick-up Cover Destick-up Cover
	2.5
	Courte 5.0
	Beuseal
Bottom of Boring 910	Grout "
sample data Depth Number/Type Depth Number/Type NO/SAMD(in-	28.0
	30.0
	40.0
CS = Continuous Sampler AS = Auger Sample	aquadril

MONIN KING WELL / PIEZOMETER CONSTRUCTION DOCUMENTATION FORM

Disposal site name City of Muscatine C & D Landfill Permit # 70 -SDP-4- 78 Well or Piezometer # MW-3 Date started 10/28/93 Date completed 10/28/93 A. Surveyed Locations and Elevations Well Installation, continued: Locations (± 0.5 ft.): Specify corner of site Survey grid Distance and direction Filter pack: Material Muscatine #0-C sand along boundary 7023.7 N Grain size Effective size = 0.930 m Volume 5.3 c.f.
Seal (minimum 3 ft. length above Distance and direction from boundary to well 10479.9 E filter pack): Material Bentonite granules Placement method Poured Elevations (±0.01 ft. MSL): Volume 1.2 c.f. Ground surface_____ 638,30 * Top of protective casing 640.37 Top of well casing 640.36

Benchmark elevation 723.29 Backfill (if different from seal): Material Same as seal Placement Method Benchmark descriptionArrowhead bolt at hydrant at Newell & Kindler Sts. Volume *Measured at hingé line Surface seal design: B. Soil Boring Information Material of protective casing: 4" square steel set in concrete Name and address of construction Material of grout between protective company Aquadrill, Inc. R.R. 2, Box 18 casing and well casing: Iowa City, IA 52240 Bentonite Name of driller Jeff Joslyn Protective cap: Drilling method Hollow stem auger Material Steel (not airtight) Vented? Y/N_____ Locking? Y/N_Y Drilling fluid None Bore hole diameter 9"
Soil sampling method ** Well cap: Material PVC expandable, not Depth of boring 21.0' Vented? Y/N_____ tightened ** Laskey continuous sampler C. Monitoring Well Installation D. Groundwater Measurement Water level (± 0.01 ft. below top of Casing material Schedule 40 PVC inner well casing) 631.90 on 1/20/94 Length of casing 12.06' Outside casing diameter 2.375" Stabilization time<u><1 week</u> Inside casing diameter 2.0" Well development method Pneumatic bailer, used until water is clear Casing joint type Flush threaded Casing/screen joint typeFlush threaded Upgradient or downgradient well? Screen material Schedule 40 PVC (see piezometric map from Hydrogeo-Screen opening size 0.010" = 0.25 mm logic study) Downgradient Screen length 10.0' Average depth of frostline 30" Depth of well 22.82'

Attachments: Driller's log. Pipe schedules and grouting schedules.
8 1/2 inch X 11 inch map showing location of all monitoring wel
and piezometers.



field boring log	
Boring No. HW-3 Date Started 10-28-93 Date Co	
subsurface stratigraphy	water levels
☐ 4" Flight Augers ☐ 4%" ID H.S. ☐ 6%" ID H.S.	While Orilling
From To Description See MW-1 For Soils Log	0 Hours A.B.
0 7.8 HATA drilling Brick Concrete	Well details G Stick-up Cover O Flush Cover
	2.5
	O Grade MISTIR
Bottom of Boring 2/0	-slepley is
Depth Number/Type Depth Number/Type	8.0
	10.0
	20.0
CS = Continuous Sampler AS = Auger Sample	aguadril

			Γ				Ī		Page 1 of 2
CaC03	X RECOVERY	K (cm/sec)	MN-3	MH-2	I-MM	ELEVATION (1t, msl)	DEPTH (feet)	LITHOLOGY	MATERIALS DESCRIPTION
	50			Ţ	Ţ	 634.0			O to 7 FILL Sandy silty clay. Yellow brown and dark brown, mottled. Disturbed material. Minor content of brick fragments.
-	100		¥ (555)			829.0	- - - 10		7 to 17 SILTY ALLUYIUM Sandy clayey silt, trace gravel. Leached. Dark brown from 7 to 8 feet. Topsoll.
-	80					0010	-		Medium gray from 8 to 17 feet, with yellow to orange brown oxidized mottles below 15 feet.
_	75	3.7 X 10 ⁻³ Bail test				6 24.0	1		Transitional contact to underlying unit. 17 to 18.5 SANDY ALLUVIUM
						619.0	- 20 -	0000	Very silty, fine to medium sand. Dark gray. Leached. 18.5 to 25 SANDY TILL
+	60					6 14.0	- 25 -	000000	Clayey silty sand, trace gravel. Dark gray. Leached from 18.5 to 20 feet. Diagonal sand seams within interval from 20 to 21.5 feet, fracture fill. Seams are 1/16 to 1/2 inches thick. Unleached below 20 feet.
+	26					609.0	- 30 -	14.0 1.0	25 to 30 TILL WITH INTRATILL SAND SEAMS Sandy silty clay, trace gravel. Dark gray. Unleached. Due to sample loss, the number and thickness of sand seams are unknown.
+	33	1.6 X 10 ⁻⁴ Bail test				604.0	- 35		Sand is light gray, fine, unleached. 30 to 40 INTRATILL SAND LENS Recovered portion is very slity, very fine sand. Medium gray, unleached.
+	26					599.0	40		40 to 45 MARSH DEPOSITS
-	82					594.0	- - -45		Organic silty clay, with plant fragments from 40 to 42 feet. Very dark gray. Leached. Interlayered sand and organic silty clay below 42 feet. Sand is medium gray, very fine, leached. 2" organic layers at 42.8 and 43.5 ft
-	78					589.0	-50		45 to 48 SAND Silty, very fine sand. Light gray. Leached. May be alluvium associated with overlying marsh deposits.
		<u> </u>					•	le Landfill	LOG OF MW-1, MW-2, MW-3
					ECT NUM	JCI1	520-J		
1				1		_ NOITAY		7 Feet MS .0 Feet	L LOCATION Muscatine, Iowa GEOLOGIST Barbara Torney
l				TOTA	AL DEPTH	OF HOLE			PEOCOGIS!

.

.


I

					T				Page 2 of 2
CaC03	X RECOVERY	K (cm/sec)	MN-3	MM-2	MW-1	ELEVATION (ft, msl)	DEPTH (feet)	LITHOLO BY	MATERIALS DESCRIPTION
+	22					5 84.0	- - - -—55	000000	48 to 60 TILL Sandy silty clay, trace gravel. Dark gray. Leached from 48 to 50 feet. Unleached below 50 feet.
+	26				Ø		-	0000	
		· · · · - 5				5 79.0	60 - -	V & V	80 to 62 INTRATILL SAND LENS Silty, fine to medium sand. Medium gray. Unleached.
+	76	2.0 X 10 ⁻⁵ Ball test 1.8 X 10 ⁻⁸ Laboratory				574.0	- 65	DODO	62 to 100 TILL Sandy clayey silt, trace gravel. Dark gray. Unleached.
						- 5 89.0	- 70 -	00000	Bag samples from mud rotary drilling below 65.0 feet.
						5 64.0	- - 75	0000	
						5 59.0	- - -80	00000	
						5 54.0	- 8 5	0000	
						549.0	- - -90	0000	
					·	544.0	- 95	0000	
						539.0	-10	0.00	Battom of borehole at 100.0 feet.
-	٠	٠	1	1 200	ECT Co	nstruction	Rubb	le Landlill	
}					ECT NUM				LOG OF MW-1, MW-2, MW-3
					FACE ELE			7 Feel MS	L LOCATION Muscatine, Iowa
-				1	AL DEPTH			.0 Feet	GEOLOGIST Barbara Torney
ı				1 1017	אנ טברוח	OF HULE			

MONI'L RING WELL / PIEZOMETER CONSTRUCTION DOCUMENTATION FORM

A. <u>Surveyed Locations and Elevations</u>	
Locations (± 0.5 ft.):	Well Installation, continued:
Specify corner of site Survey grid	-1-1
Distance and direction	Filter pack:
along boundary 7229.9 N	Material Muscatine #0-C sand
	Grain size Effective size = 0.930 m
Distance and direction	Volume 5.1 c.f.
from boundary to well 10445.3 E	Seal (minimum 3 ft. length above
	<pre>filter pack): Material Bentonite granules</pre>
	Placement method Poured
Elevations (±0.01 ft. MSL): Ground surface 691.29 * Top of protective casing 693.23	Volume 2.3 c.f.
t man of metactive casing 693 23	VOI dime
Top of well casing 693.22	Backfill (if different from seal):
Top of well casing 693.22 Benchmark elevation 723.29	Material Same as seal
Benchmark descriptionArrowhead bolt	Placement Method
at hydrant at Newell & Kindler Sts.	Volume
*Measured at hinge line	
B. Soil Boring Information	Surface seal design:
	Material of protective casing:
Name and address of construction	4" square steel set in concrete
company Aquadrill, Inc.	Material of grout between protective
R.R. 2, Box 18	casing and well casing:
Iowa City, IA 52240	Bentonite
Name of driller <u>Jeff Joslyn</u>	Protective cap:
Drilling method Hollow stem auger	Material Steel (not airtight)
Drilling fluid None	Vented? Y/N Locking? Y/N_Y
Bore hole diameter 9"	Well cap:
Soil sampling method **	Material <u>PVC expandable, not</u> Vented? Y/N tightened
Depth of boring 23.0'	venceu: 1/N cignceneu
** Laskey continuous sampler C. Monitoring Well Installation	D. Groundwater Measurement
C. Monitoring well installation	D. Gloundwatel Measuromens
Casing material Schedule 40 PVC	Water level (± 0.01 ft. below top of
Length of casing 14.43'	inner well casing) 675.17 on 1/20/9
Outside casing diameter 2.375"	Stabilization time <1 week
Inside casing diameter 2.0"	Well development method Pneumatic
Casing joint type Flush threaded	bailer, used until water is clear
Casing/screen joint typeFlush threaded	
Screen material Schedule 40 PVC	Upgradient or downgradient well?
Screen opening size 0.010" = 0.25 mm	(see piezometric map from Hydrogeo-
Screen length 10.0'	logic study) <u>Downgradient</u>
Depth of well 25,04'	Average depth of frostline 30"

Form #542-127



field boring log	÷
Project Muscative CAD land Fill	
Boring No. HW-4 Date Started 10-28-93 Date Contilled by AYA Troy Logged by AY Rig Contilled by AYA Rig Contilled by AYA Troy Logged by AY	
subsurface stratigraphy	water levels
04" Flight Augers 04%" ID H.S. 06%" ID H.S.	While Drilling
Description 0 6.5 Fill" Brick + Concrete Wood 5 6.5 Steel"	O Hours A.B.
120 LT Brown & Clay LT Brown & Fire- Hed Stand	Well details Stick-up Cover Oflush Cover
	25
	Derodo Miller S. O. S. O
Bottom of Boring	Holephy in
Sample data Depth Number/Type Depth Number/Type 10-15 1-25	10.5
15-20 2-C5 95-14.5 1-C5	
145-145_2-c5	
	225
	23.0
CS = Continuous Sampler AS = Auger Sample	aquadril

									Page 1 of 1
C9C03	* RECOVERY	K (cm/sec)			MW-4	ELEVATION (ft, msl)	DEPTH (feet)	LITHOLOBY	MATERIALS DESCRIPTION
	0					6 86.0	- 5		O to 6.5 WASTE Drillers report: "Fill", brick, concrete, wood, steel. "Fill" may refer to landfill cover, but no thickness was reported.
	0				.	6 81.0	- - 		8.5 to 23 EOLIAN SAND (Drillers report: Lt. Brown slity clay 8.5 to 8.5 feet, no sample). Very slity fine sand. Yellow brown. Leached. Light gray with orange mottles from 10 to 13 feet. Cohesive.
-	100		·		1 THE SECOND	678.0	- - 5		Not silty below 13.0 feet. Light brown to cream-colored.
-	54	1.5 x 10 ⁻³ Ball test				8 71.0	- - 20		·
							_		Bottom of boring at 23.0 feet.
-	32				E L		<u> </u>		Bottom of borning at 25.0 feet.
						-686.0	25 		
						8 61.0	-30 -		
						656.0	- 35 -		
						851.0	- 40 -)	
						848.0	- - - - -		
							-		
1						841.0	-50		
-		J	PROJE	PROJECT _Construction Rubble Landfill			le Landfill	100.05.444.4	
1			PROJ	PROJECT NUMBER				LOG OF MW-4	
Ì				SURFACE ELEVATION 691.29 Feet MSL				9 Feet MS	SL LOCATION Muscatine, Iowa
\					TOTAL DEPTH OF HOLE				GEOLOGIST Barbara Torney

.


MONITO ING WELL / PIEZOMETER CONTRUCTION DOCUMENTATION FORM

Disposal site name <u>City of Muscatine C</u> Well or Piezometer <u># MW-5</u> Date st	& <u>D Landfill</u> Permit <u># 70</u> -SDP- <u>4- 78</u> Parted 10/29/93 Date completed 11/2/93
A. <u>Surveyed Locations and Elevations</u>	
Locations (± 0.5 ft.): Specify corner of site Survey grid Distance and direction along boundary 7433.6 N Distance and direction from boundary to well 10488.8 E	<pre>Well Installation, continued: Filter pack: Material Muscatine #0-C sand Grain size Effective size = 0.930 mm Volume 3.3 c.f. Seal (minimum 3 ft. length above filter pack): Material Bentonite grout</pre>
Elevations (±0.01 ft. MSL): Ground surface 714.70 * Top of protective casing 716.81 Top of well casing 716.80 Benchmark elevation 723.29 Benchmark description Arrowhead bolt at hydrant at Newell & Kindler Sts.	Placement method Tremied Volume 25.5 c.f. Backfill (if different from seal): Material Same as seal Placement Method Volume
*Measured at hinge line B. Soil Boring Information Name and address of construction company Aguadrill, Inc. R.R. 2, Box 18	Surface seal design: Material of protective casing: 4" square steel set in concrete Material of grout between protective casing and well casing:
Iowa City, IA 52240 Name of driller_Jeff Joslyn Drilling method_Hollow stem auger Drilling fluid_None Bore hole diameter_9" Soil sampling method_** Depth of boring_75.0'	Bentonite Protective cap: Material Steel (not airtight) Vented? Y/N Locking? Y/N_Y Well cap: Material PVC expandable, not Vented? Y/N tightened
** Laskey continuous sampler C. Monitoring Well Installation	D. Groundwater Measurement
Casing material Schedule 40 PVC Length of casing 71.10' Outside casing diameter 2.375" Inside casing diameter 2.0" Casing joint type Flush threaded Casing/screen joint typeFlush threaded Screen material Schedule 40 PVC Screen opening size 0.010" = 0.25 mm Screen length 5.0' Depth of well 77.28'	Water level (± 0.01 ft. below top of inner well casing) 665.85 on 1/20/94 Stabilization time 3 months (?) Well development method Pneumatic bailer, used until water is clear Upgradient or downgradient well? (see piezometric map from Hydrogeologic study) Upgradient Average depth of frostline 30"
	dules and grouting schedules. showing location of all monitoring wells

and piezometers.

Form #542-127;

ELEVATIONS: 1 0.01 FT. MSL DEPTHS: 1 0.1 FT. FROM GROUND SERFACE SPACE TO ATTACH ENTIRE SOIL BORING LOG (SHOW SCREENL INTERVAL AND FILTER PACK INTERVAL



field boring log							
Project tiuscative C+D LANDETICC							
Boring No. MW-5 Date Started 10-29-9.3 Date Co	-						
1:-26	water levels						
subsurface stratigraphy 37-47	20 While Drilling						
From To Description O 4.0 KBN \$CLAY	0 Hours A.B.						
4.0 9.0 CT BIN SAM SCLAT	130 72 Hr. A.B.						
9.0 31.0 LT Brown Fine-Med SANTECT	well details						
31.0 31.0 Clive week & Clay Tsaud Corave	Stick-up Cover						
3900 45.0 LT Brown Five-HEd SALA	Flush Cover						
45.0 SK Brey SCLAN USANK VErwel	2.5						
	Ø Grade MISTING						
	Concrete						
	1-5·0						
	Ben						
	Seal \$						
Bottom of Boring 75,0	Mag T W						
	Grow!						
sample data Depth Number/Type Depth Number/Type							
0-50 1-65 50-55 11-65	67.5 - H						
5-00 2-CS 55-60 12-US							
10-15 3-05 60-65 13-05							
15-20 4-05 65-70 14-05	69.C						
20-25 5-05 70-75 15-05							
25-30 6-65	1:1=1:						
30-35 7-65	740						
35-90 65-19 1/1-46 0-16	750						
16-66 10-65	1						
CS = Continuous Sampler AS = Auger Sample	aquadril						

.


...

MONITORING WELL / PIEZOMETER CONSTRUCTION DOCUMENTATION FORM

Disposal site name <u>City of Muscatine C</u> Well or Piezometer # <u>MW-6</u> Date sta	& D Landfill Permit # 70 -SDP-4- 78 arted 11/3/93 Date completed 11/3/93
A. Surveyed Locations and Elevations	·
Locations (± 0.5 ft.):	Well Installation, continued:
Specify corner of site Survey grid	
Distance and direction	Filter pack:
along boundary 7431.0 N	Material Muscatine #0-C sand
	Grain size <u>Effective size = 0.930 m</u>
Distance and direction	Volume 5.3 c.f.
from boundary to well 10483.2 E	Seal (minimum 3 ft. length above
	filter pack):
	Material Bentonite grout
Elevations (±0.01 ft. MSL):	Placement method Tremied
Elevations (±0.01 ft. MSL): Ground surface 714.65 * Top of protective casing 716.74 Top of well casing 716.63	Volume 12.3 c.f.
* Top of protective casing 716.74	
Top of well casing 716.63	Backfill (if different from seal):
Benchmark elevation 723.29	Material Same as seal
Benchmark descriptionArrowhead bolt	Placement Method
at hydrant at Newell & Kindler Sts.	Volume
*Measured at hinge line	Curfo an anni dogiane
B. Soil Boring Information	Surface seal design: Material of protective casing:
	4" square steel set in concrete
Name and address of construction	Material of grout between protective
company Aquadrill, Inc.	casing and well casing:
R.R. 2, Box 18 Iowa City, IA 52240	Bentonite Bentonite
Name of driller Jeff Joslyn	Protective cap:
Drilling method Hollow stem auger	Material Steel (not airtight)
Drilling fluid None	Vented? Y/N Locking? Y/N_Y
Bore hole diameter 9"	Well cap:
Coil campling method **	Material PVC expandable, not
Soil sampling method ** Depth of boring 48.0'	Vented? Y/N tightened
** Laskey continuous sampler	
C. Monitoring Well Installation	D. Groundwater Measurement
Casing material Schedule 40 PVC	Water level (± 0.01 ft. below top of
Length of casing 38.98'	inner well casing) 674.88 on 1/20/94
Outside casing diameter 2.375"	Stabilization time 1 month (?)
Inside casing diameter 2.0"	Well development method Pneumatic
Casing joint type Flush threaded	bailer, used until water is clear
Casing/screen joint typeFlush threaded	
Screen material Schedule 40 PVC	Upgradient or downgradient well?
Screen opening size 0.010" = 0.25 mm	(see piezometric map from Hydrogeo-
Screen length 10.0'	logic study) Upgradient
Depth of well 48.95'	Average depth of frostline 30"

Attachments: Driller's log. Pipe schedules and grouting schedules.
8 1/2 inch X 11 inch map showing location of all monitoring well
and piezometers.

Form #542-127



field boring log	
Boring No. HW-6 Date Started 11-3-93 Date Co	
subsurface stratigraphy Output Augura (10 H.s. (10 H.s.) From To Description See HW-5 for Soils log	water levels While Drilling O Hours A.B Hr. A.B.
	Well details Stick-up Cover Flush Cover 2.5 Grade MS/N S.O Benga
Bottom of Boring 48.0 sample data	Grout &
Depth Number/Type Depth Number/Type	35.0
	37.0
	47.0
CS = Continuous Sampler AS = Auger Sample	aquadril


i

MONIN .ING WELL / PIEZOMETER CON_TRUCTION DOCUMENTATION FORM

Disposal site name <u>City of Muscatine C</u> Well or Piezometer <u># MW-7</u> Date st	& D Landfill Permit # 70 -SDP-4- 78 arted 11/3/93 Date completed 11/3/93
A. Surveyed Locations and Elevations	
Locations (± 0.5 ft.): Specify corner of site Survey grid Distance and direction along boundary 7428.0 N Distance and direction from boundary to well 10477.4 E	Well Installation, continued: Filter pack: Material Muscatine #0-C sand Grain size Effective size = 0.930 mm Volume 5.3 c.f. Seal (minimum 3 ft. length above
Elevations (±0.01 ft. MSL): Ground surface	filter pack): Material Bentonite granules Placement method Poured Volume 1.2 C.f. Backfill (if different from seal): Material Same as seal Placement Method
at hydrant at Newell & Kindler Sts. *Measured at hinge line B. Soil Boring Information Name and address of construction company Aquadrill, Inc.	Volume Surface seal design: Material of protective casing: 4" square steel set in concrete Material of grout between protective
R.R. 2, Box 18 Iowa City, IA 52240 Name of driller Jeff Joslyn Drilling method Hollow stem auger Drilling fluid None Bore hole diameter 9" Soil sampling method ** Depth of boring 21.0'	casing and well casing: Bentonite Protective cap: Material Steel (not airtight) Vented? Y/N Locking? Y/N_Y Well cap: Material PVC expandable, not Vented? Y/N tightened
** Laskey continuous sampler C. Monitoring Well Installation Casing material Schedule 40 PVC	D. Groundwater Measurement Water level (± 0.01 ft. below top of
Length of casing 12.25' Outside casing diameter 2.375" Inside casing diameter 2.0" Casing joint type Flush threaded Casing/screen joint typeFlush threaded Screen material Schedule 40 PVC Screen opening size 0.010" = 0.25 mm Screen length 10.0' Depth of well 22.55'	inner well casing) 698.15 on 1/20/94 Stabilization time <1 day Well development method Pneumatic bailer, used until water is clear Upgradient or downgradient well? (see piezometric map from Hydrogeo- logic study) Upgradient Average depth of frostline 30*
	dules and grouting schedules. showing location of all monitoring well

Form #542-127

ELEVATIONS: 1 0.01 FT. MSL DEPTHS: 1 0.1 FT. FROM GROUND SERFACE SPACE TO ATTA' ENTIRE SOIL BORING LOG (SHOW SCREENLO INTERVAL AND FILTER PACK INTERVA



field boring log	
Project Muscrtine C+D lauratice	// 2_S ?
Boring No. MW-7 Date Started 11-3-93 Date C	
	water levels
subsurface stratigraphy	Water levels
☐ 4" Flight Augers · ☐ 4%" ID H.S. ☐ 6%" ID H.S. From To Description	O Hours A.B.
See MW-5 for Soils	Hr. A.B.
	well details
	☐ Stick-up Cover □ Flush Cover
	2.5
	Carret
	1 - 5.00 - P
Bottom of Boring 200	41-1
sample data	Berseal
Depth Number/Type Depth Number/Type	8,0
190	
- Wolfmalia	
	10.0
	<u>20.0</u> [].
	210
CS = Continuous Sampler AS = Auger Sample	aquadril

ŀ

I

			1				-		Page 1 of 2
CaCO3	* RECOVERY	K (cm/sec)	MH-7	MM-8	9-MM	ELEVATION (ft, msl)	DEPTH (leet)	LITHOLOGY	MATERIALS DESCRIPTION
-	74					7 10.0	1 1 1 5		O to 8 LOESS Clayey silt, trace fine sand. Leached. Medium brown from O to 3.5 feet, topsoil. Yellow brown from 3.5 to 8 feet.
_	82						1 1 1		
-	38					7 05.0	- 1 0		9 to 29 EOLIAN SAND Fine sand. Leached. Yellow brown.
		1.3 X 10 ⁻³ Bail test	#####################################			7 00.0	- 		Very silty fine sand, cohesive, from 15 to 17 feet. Yellow gray with orange oxidized mottles.
_	76			•		8 95.0	- 20		Fine sand below 17 feet. Yellow brown.
-	50					690.0	- - - -25		Light brownish gray from 25 to 29 feet.
-	86						1 1 1 1	V o V	
-	82	3.0 X 10 ⁻⁹ Laboratory				6 85.0	30 - - -	D00000	29 to 35 TILL Sandy silty clay, trace gravel. Leached. Blue gray with brown mottles (Paleosol ?) from 29 to 32 feet. Yellow brown from 32 to 35 feet.
-	42					680.0	- 3 5 - - -		35 to 44 INTRATILL SILT AND SAND LENS Very sandy silt grading downward to to fine sand below 37 feet. Light brown. Leached.
	54	5.8 X 10 ⁻⁵	·	¥		675.0	40 		LIGHT DIOMIL LEGGIEG.
		Bail test				6 70.0	45	V 00 0	44 to 75 TILL Sandy silty clay, trace gravel. Leached. Yellow brown from 44 to 45 feet.
-	88				1	685.0	50	0.00	Dark gray below 44 feet.
	PROJECT Construction Rubble Landfill LOG OF MW-5, MW-8, MW-7								
				1	ECT NUMB		520-J		
				l l	ACE ELEV			O Feet MS O Feet	
1				TOTA	IL DEPTH	OF HOLE	10,0		GEOLOGIST Barbara Torney

į

	T 1					1			Page 2 of 2
CaCO3	* RECOVERY	K (cm/sec)	MW-7	WW - 68	MM-5	ELEVATION (ft, msl)	DEPTH (feet)	LITHOLOGY	MATERIALS DESCRIPTION
							-	700	Unleached from 50 to 80 feet.
+	58			-			-	000	
						660.0	- 55	000	
						- 000.0	- "	V 0 V	
+	100						-	0 00	
						855.0	- 80	000	Leached from 60 to 75 feet.
								000	2220,020 110.11 00 10 10 120.1
-	100						-	0 00	
						-650.0	- 85	0.00	
		,					-	Do	·
-	100						-	V 60	
						-645.0	70	0 00	
_	400	1.8 X 10 ⁻⁵ Ball test					-	200	·
-	100	ball test					F	000	Bottom of borehole at 75.0 feet.
						640.0	75 -		Bottom of bot Endie Bt 76.6 foot.
							-		
			}			635.0	80		
							E	•	
							F	<u> </u>	·
		<u> </u>				630.0	85		
		}					-	·	
							-		
					ŀ	625.0	-80		
							E		
							F		
						B20.0	- 95		
							ļ		
						815.0	<u></u>	d	
-		<u> </u>	<u> </u>	PROJ	ECT _CC	nstruction	1	1	
PRI				PRO	ECT NUM	BER	1520-	<u> </u>	
	SURFACE ELEVATION 714.70 Feet MSL LOCATION Muscatine, Iowa						SL LOCATION Muscatine, Iona		
				TOT	AL DEPTH	OF HOLE	75.	U Feet	GEOLOGIST Barbara Torney

; . ; .

field boring log	
Boring No. 117-8 Date Started 11-2-93 Date Co	
Drilled by Troy In Logged by In Rig Dr	RU-S/
subsurface stratigraphy	water levels 37.0 while Drilling
04" Flight Augers 24%" ID H.S. U6%" ID H.S. From To Description , / / / / / / / / / / / / / / / / / /	O Hours A.B.
2.5 Fill Courrete Labor Brick	Hr. A.B.
41.5 "Soil" SAND	well details Stick-up Cover Flush Cover Horox
10-BAS GRAND BANK 8-BAS HALPLY Air Scilling "/41/2" BUTTOM BIT	S.O Grade MANA
Bottom of Boring 460 sample data	Holephy "
Oepth Number/Type Depth Number/Type 41.5-460 1-05	21.5
	30.5
	40.5 41.0 respon
CS = Continuous Sampler AS = Auger Sample	4640400111

Caco3	RECOVERY	K (cm/sec)		LPZ-8	ELEVATION (ft, mst)	DEPTH (feet)	LITHOLOBY	Page of (MATERIALS DESCRIPTION
	×				ᇤ) SE	=	·
	0					- -		O to 2.5 LANDFILL COVER Orillers report: Dark brown silty clay with sand "fill". 2.5 to 41.5 WASTE
	0				6 83.0			Drillers report: "Fill" concrete slabs, brick.
	0				6 78.0	1 0 - - -		
					6 73.0	- 1 5 -		
	0				8 88.0	- 20 -		
	0				6 63.0	- 25 -		
	0				-6 58.0	- - 30		
	0				653.0	- - - -35		
	0				848.0	- - -		
-	89				040.0	-		41.5 to 44 SILTY ALLUVIUM Slity clay, trace sand. Medium gray. Leached. No sample suitable for permeabilty test.
-		4.4 X 10 ⁻⁹ Laboratory			643.0	-45 - -	000	44 to 48 TILL Sandy slity clay, trace gravel. Yellow brown. Leached. Bentonite seal in borehole from 41 to 48 feet.
					638.0	1	1	Bottom of borehole at 48.0 feet.
		. 1		OJECT CO				LOG OF LPZ-8
			sı	RFACE ELE	_ NOITAY	687.6	35 Feet MS	SL LOCATION Muscatine, Iowa
			т	TAL DEPTH	OF HOLE	48.	0 Feet	6EOLOGIST Barbara Torney

•

:

APPENDIX

hadraulg conductivities.

H. R. GREEN LAB TESTING CONSTRUCTION - DEMOLITION LANDFILL TERRACON JOB NO. 06941003 H.R. GREEN JOB NO. 714520

Sample S	ample Description	Dry Density	Moisture Content	Coefficient of Permeability cm/sec.
LPZ-8 45 - 46'	Brown Gray Sandy Lean to Fat Clay, Trace Gravel	115.2	17.9	4.4 X 10 ⁻⁹
MW-1 62 - 63'	Gray Sandy Lean Clay, Trace Gravel	131.0	8.3	1.8 X 10 ⁻⁸
MW-5 33- 34'	Gray Brown Sandy Lean to Fat Clay	103.7	22.5	3.0 X 10 ⁻⁹

Note:

The permeability tests were performed in a fluid filled chamber with the sample surrounded by a flexible membrane. Back pressure was used to aid in saturating the sample, and a water head of 5 psi was used for percolation.

GREEN ENVIRONMENTAL SERVICES	Client: CONSTRUCTION RUBBLE LANDFILL	JBBLE LANDFILL
oject	Location: MUSCATINE, IOWA	٧A
	MW-1	
10. [11111]		DATA SET: 2MW1.ADT 02/10/94
(1.	AQUIFER Unconfined SOLUTION BOUWER-RIC	AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: JANUARY 20, 1994
t) uwot	MW-1 OBS.	MW-1 OBS. WELL: NA
Drawc	ESTI K = yo =	ESTIMATED PARAMETERS: K = 4.0303E-05 ft/min y0 = 9.075 ft
	TEST HO = 100 HO = 10	TEST DATA: H0 = 10.83 ft rc = 0.083 ft rw = 0.375 ft L = 9. ft
1.	11.	2.75 ft 2.75 ft

:

2

Client: CONSTRUCTION RUBBLE LANDFILL GREEN ENVIRONMENTAL SERVICES Project No.: 714520-J Location: MUSCATINE, IOWA MW-2DATA SET: 2mw2.adt 10. 02/10/94 AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: JANUARY 20, 1994 Drawdown (ft) TEST WELL: MW-2 OBS. WELL: 1. ESTIMATED PARAMETERS: K = 0.0003232 ft/miny0 = 3.18 ftTEST DATA: H0 = 3.224 ftrc = 0.083 ftrw = 0.375 ftL = 10. ftb = 35.76 ftH = 35.76 ft0.1 3. 2. 0. 1. 5. 6. Time (min)

DATA SET: H = 13.6 ft DATA SET: DATA SET:	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		Drawdown (ft)
	8-	WM	
	Location: MUSCATINE	CHOIANAC	Project No : 714520-J
N RUBBLE LANDFILL	Client: CONSTRUCTIO	Sanudas	Truncation 1220

¥ 4

1

Client: CONSTRUCTION RUBBLE LANDFILL GREEN ENVIRONMENTAL SERVICES Location: MUSCATINE, IOWA Project No.: 714520-J MW-4DATA SET: mw4.adt 10. 02/10/94 AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: JANUARY 20, 1994 Drawdown (ft) TEST WELL: MW-4 OBS. WELL: NA ESTIMATED PARAMETERS: K = 0.003012 ft/min0.1 y0 = 1.632 ftTEST DATA: H0 = 2.514 ftrc = 0.083 ftrw = 0.083 ftL = 6.88 ftb = 6.88 ftH = 6.88 ft0.01 2. 0. 0.5 1. 1.5 2.5 3. 3.5 Time (min)

47.4

TEST DATE: JANUARY 20, 1994 TEST WELL: WW-5 OBS. WELL: K = 8.7934E-05 ft/day V0 = 24.35 ft TEST DATA: TEST DATA: L = 8. ft L = 8. ft L = 8. ft L = 8. ft L = 8. ft	25. 66. 77.	0 0	Drawdown (ft)	
OS/S4/94 Bouwer-Rice Bouwer-Rice	- - - - - - - - - - - - - - - - - - -		100.	
DATA SET:				
	9 -	WM		
AWOI,	Location: MUSCATINE		1-023417 : ON 3	
N RUBBLE LANDFILL	Client: CONSTRUCTIO	ICES	N ENAIKONWENTAL SERV	СВЕЕ

•

.

٤ ٢

GREEN ENVIRONMENTAL SERVICES Client: CONSTRUCTION RUBBLE LANDFILL Location: MUSCATINE, IOWA Project No.: 714520-J MW-6DATA SET: 3MW6.ADT 02/10/94 AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: JANUARY 20, 1994 Drawdown (ft) TEST WELL: MW-6 OBS. WELL: 1. NA ESTIMATED PARAMETERS: K = 0.0001149 ft/miny0 = 2.523 ftTEST DATA: H0 = 3.383 ftrc = 0.221 ftrw = 0.375 ftL = 7.23 ftb = 7.23 ftH = 7.23 ft0.1 15. 20. 25. 30. 35. 40. 5. 10. 0. Time (min)

11 27 4 = 1 11 27 21 = d 11 27 4 = H	8 .9	1.0 S. S. Time (mim)				
TEST DATA: HO = 1.722 ft rc = 0.375 ft	200000000000000000000000000000000000000					
ESTIMATED PARAMETERS: y0 = 1.301 ft	- - - - -	Drawdov do value do v				
TEST WELL: OBS. WELL: NA-7 NA-7 NA-7	-	Drawdown (ft)				
TEST DATE: Soundined AQUIFER TYPE:	- - - - -					
DATA SET: 02/10/94	E					
L-WM						
AWOI ;	Location: MUSCATINE	Project No.: 714520-J				
ON RUBBLE LANDFILL	Client: CONSTRUCTIO	GREEN ENVIRONMENTAL SERVICES				

Buch Survey

90 g

ATTACHMENT C

Analytical Results & Summary Tables

CITY OF MUSCATINE C&D LANDFILL 70-SDP-4-78C MONITORING WELL SAMPLING RESULTS

SAMPLING DATE: 03/06/2007 D.G.W D.G.W U.G.W U.G.W D.G.W MW 2 MW 4 MW 7 PARAMETER MCL MW 3 MW 6 ug/L 5 NT NT NT NT NT Benzene * 5 NT NT NT NT NT Carbon tetrachloride * 0.6 NT NT NT NT NT 1.4-Dichlorobenzene * NT NT NT NT NT 1.2-Dichloroethane * 5 NT NT 7 NT NT 1,1-Dichloroethylene * NT NT NT NT NT 200 NT 1,1,1-Trichloroethane * $\overline{\mathsf{NT}}$ 2 NT NT NT NT Vinyl Chloride NT NT NT NT cis-1,2-Dichloroethylene 70 NT NT NT NT NT Tetrachloroethylene * 5 NT 5 NT NT $\overline{\mathsf{NT}}$ NT NT Trichloroethylene mg/L Arsenic, dissolved NT NT NT 0.05 NT NT NT NT NT NT NT Barium, dissolved 2 0.005 NT NT NT NT NT Cadmium, dissolved NT NT NT NT Chromium, dissolved 0.1 NT 1.3 NT NT NT NT NT Copper, dissolved NT NT NT NT 5 NT Zinc, dissolved NT 0.015 NT NT NT NT Lead, dissolved NT NT NT NT Mercury, dissolved 0.002 NT $\overline{\mathsf{NT}}$ NT NT NT NT Magnisium, dissolved ---0.3 0.460 2.85 0.966 0.194 DRY Iron, dissolved DRY Chloride 250 <10 64 52 62 <1.0 1.2 1.7 <1.0 DRY Nitrogen, Ammonia <10 DRY <10 27 20 Chemical Oxygen Dema NT NT NT NT NT **Phenols** NT $\overline{\mathsf{NT}}$ NT NT NT TOX DRY 7.3 7.3 7.2 7.5 6.5 - 8.5pΗ 13 DRY 10 10 14 Temperature, celsius

592

751

1520

812

DRY

Conductivity







Accreditations: Iowa DNR: 095 New Jersey DEP: IA001 Kansas DHE: E-10287

ANALYTICAL REPORT

March 14, 2007

Page 1 of 2

Work Order: 17C0276

Report To

Todd Whipple

Fox Engineering Associates, Inc. 1601 Golden Aspen Drive. Suite 103

Ames, IA 50010

Work Order Information

Date Received: 03/07/2007 3:37PM

Collector: Richard Freeman

Phone: 515-233-0000

PO Number:

Project: Muscatine Sanitary Landfill-Spring

Project Number: 6008-06A

Analyte	Re	sult	MRL	Method	Analys	t Analyzed Qualifier
7C0276-01 MW2				Matrix: Water	-	Collected: 03/06/07 17:00
Determination of Conventional Chemi	stry Parame	eters				
Chemical Oxygen Demand		mg/l	10	EPA 410.4	SAA	03/09/07 14:42
Chloride	<10	mg/l	10	EPA 9252	WAS	03/09/07 11:26
Nitrogen, Ammonia	1.2	mg/l	1.0	SM 4500-NH3 F	SAA	03/08/07 14:44
Determination of Dissolved Metals		_				00/10/05 11 40
Iron, dissolved	0.460	mg/l	0.030	EPA 6010B	LAR	03/12/07 11:43
17C0276-02 MW3				Matrix:Water		Collected: 03/06/07 17:15
Determination of Conventional Chemi						
Chemical Oxygen Demand		mg/l	10	EPA 410.4	SAA	03/09/07 14:42
Chloride		mg/l	10	EPA 9252	WAS	03/09/07 11:26
Nitrogen, Ammonia	1.7	mg/l	1.0	SM 4500-NH3 F	SAA	03/08/07 14:44
Determination of Dissolved Metals						
Iron, dissolved	2.85	mg/l	0.030	EPA 6010B	LAR	03/12/07 11:47
17C0276-03 MW4				Matrix:Water		Collected: 03/06/07 17:45
Determination of Conventional Chemi	istry Param	eters				
Chemical Oxygen Demand	20	mg/l	10	EPA 410.4	SAA	03/09/07 14:42
Chloride		mg/l	10	EPA 9252	WAS	03/09/07 11:26
Nitrogen, Ammonia	<1.0	mg/l	1.0	SM 4500-NH3 F	SAA	03/08/07 14:44
Determination of Dissolved Metals						
Iron, dissolved	0.966	mg/l	0.030	EPA 6010B	LAR	03/12/07 11:51
17C0276-04 MW6				Matrix:Water		Collected: 03/06/07 18:10
Determination of Conventional Chemi	istry Param	eters				
Chemical Oxygen Demand		mg/l	10	EPA 410.4	SAA	03/09/07 14:42
Chloride	62	mg/l	10	EPA 9252	WAS	03/09/07 11:26
Nitrogen, Ammonia	<1.0	mg/l	1.0	SM 4500-NH3 F	SAA	03/08/07 14:44
Determination of Dissolved Metals				•		
Iron, dissolved	0.194	mσ/l	0.030	EPA 6010B	LAR	03/12/07 11:56

MRL= Method Reporting Limit.







Work Order: 17C0276

March 14, 2007

Page 2 of 2

17C0276-04

MW6

Matrix:Water

Collected: 03/06/07 18:10

End of Report

Keystone Laboratories, Inc. Sue Thompson For Jeffrey King, Ph.D. Laboratory Director

/ (fevstone

☐ 600 E. 17th St. S. Newton, IA 50208 Phone: 641-792-8451

3012 Ansborough Av	Waterloo, IA 50701
	i

CHAIN OF CUSTODY RECORD

ě. Phone: 319-235-4440

•	PAGEOF

Fax: 319-235-4480 Fax: 913-321-7937 PAGE COF— www.keystonelabs.com	MAME: LAUNE BY AND ROWN NAME: LAUNE BY AND ROWN NAME: DUSCOPPY ROCYCLING ADDRESS: CITY/ST/ZIP: MASCAHAR CITY/ST/ZIP: MASCAHAR PHONE: Keystone Quote No.: (If Applicable)
Fax: 641-792-7989	NAME: COMPANY NAMADDRESS: CITY/ST/ZIP: PHONE: FAX:
LABORATORIES, INC.	SAMPLER: K, Lhar Mrgrmm SAMPLER: K, Lhar Mrgrmm SITE NAME: Musical And CE. D ADDRESS: CITY/ST/ZIP:

NO. TABORATORY SAMPLE NUMBER	9/	63	03	po po					Contact Lab Prior to Submission			FORM: CCR 7-97
LAB USE ONLY LABORATORY WORK ORDER NO. SAMPLE TEMPERATURE UPON RECEIPT: "C SY SY NECEIPT: "C NU SAMPLE CONDITION/COMMENTS								40.0			!	
ANALYSES REQUIRED								Tum-Around:) Januard	Remarks:	· W.	Pink - Sampler Copy
XIRTAM GRAB/COMPOSITE 1) 1) 1)	NXX	((-	Date	Time	12te 7-07	Time 3: 37 P.M.	Yellow - Lab Copy •
SAMPLE LOCATION O O O	Monatorina Nel/2 3	(38)	h \ \	(9)				Received by: (Signature)	opp	Received for Lab by: (Signature)	Denetopping	•
JMIT	107 SUOPM	EVS PM	WHS/SS	610Am					Time 3300	Date	Time	
CLIENT ET SAMPLE NUMBER	12/2	nw3 /	N 4 4 M	mus				Relinquished by: (Signature)	Paho Framo	Relinquished by: (Signature)		

Site Name CITY of Musc				70-5DF	2-4-18 <u>C</u>	
Monitoring Well/Piezometer No.	MW-2		pgradient owngradient		· · · · · · · · · · · · · · · · · · ·	
Name of person sampling	<u> </u>		omigradio <u>m</u>			
A) MONITORING WE	LL/PIEZOMETE	R CONDITIO	NS			
Well/Piezometer Pro If no, explain	operly Capped?_	<u>405</u>		nding Wate es, expla <u>in</u>	r or Litter? No	
B.) GROUNDWATER	ELEVATION ME	ASUREMEN	Γ (+/- 0.01 foo	t, MSL)		
Elevation: Top of	nner well casing	640.86	Ground E		638.70	
Depth of Well Equipment Used	42.16 Ealistet	Inside C	asing Diamete	er (in inch <u>es</u>) 2.0"	
• •						
Ground	water Level (+/-	0.01 foot belo	w top of inner	casing, MS	: L) :	
	Date/Time		epth to roundwater		oundwater evation	
Before Purging *After Purging	3/6/07		8.0			
*Before Sampling	3/6/07 5:00	gon _	8.5			
C.) WELL PURGING						
Quantity of Water No.of Well Volum Was well pumped	es (based on cur					
Equiprnent used: Bailer type Pump type If not dedica	Disposable		'Dedicated 'Dedicated			
D.) FIELD MEASURE						
pH Equipn Specific Condition	s (after stabilizati 10 nent Used HA 7,3 nent Used HA	on): U CH COMPA CH COMF	<u>'</u>	T PAL CET PAL	1	
Comments						
NOTE: Attach Lab	oratory Report ar ater monitoring po	nd 8-12" x 11" pints. One ma	site plan show	wing location	ns of all surface a	and

Site Name CITY of Musc	TINE CED	<i>Landfill</i> Permit No.	70-5	SDP-4-78	<u> </u>
Monitoring Well/Piezometer No.	MW-3	Upgradien Downgrad			
Name of person sampling	RMF		ient /		
A.) MONITORING WE	LL/PIEZOMETER	CONDITIONS			
Well/Piezometer Pro If no, explain	operly Capped?	YP5	_Standing V _If yes, expl	Vater or Litter?	N₀
B.) GROUNDWATER	ELEVATION MEA	SUPEMENT (+/- 0.0	1 foot, MSL)		
Elevation: Top of i Depth of Well Equipment Used	nner well casing 22 · O(e SOLINST	640.36 Gro Inside Casing Dia	und Elevatio ameter (in ind	n 638,30	
Ground	water Level (+/- 0.	01 foot below top of	inner casing,	MSL):	
	Date/Time	Depth to Groundwa	ter	Groundwater Elevation	•
Before Purging *After Purging *Before Sampling	3/6/07 3/6/07 5:15p	8·1 17·5 ~ 8·1	-		
C.) WELL PURGING					
Quantity of Water No.of Well Volum Was well pumped	es (based on curre	ell (gallons) 7.5 ent water level) 3 No			
Equipment used: Bailer type Pump type If not dedica	Disposess	'Dedic	cated Bailer cated Bailer		
D.) FIELD MEASURE	MENT				
pH Equipn Specific Condition	s (after stabilizatio 10 nent Used HAC 73 nent Used HAC		BCKET 7	L AL TAL	
Comments					
NOTE: Attach Lab groundwa	oratory Report and ater monitoring poi	I 8-12" x 11" site plar nts. One map per sa	n showing loo mpling round	cations of all surf I.	ace and

Monitoring Well/Piezometer No.	MW-4	Upgradient	
Name of person sampling	RMF	Downgradie <u>nt</u>	
A.) MONITORING WE	LL/PIEZOMETER C	ONDITIONS	
Well/Piezometer Pro If no, explain	operly Capped?		ling Water or Litter? No
B.) GROUNDWATER	ELEVATION MEASI	UREMENT (+/- 0.01 foot, I	MSL)
Elevation: Top of Depth of Well Equipment Used	inner well casing (24.43 SOUNST	93·22 Ground Ele Inside Casing Diameter (vation_ <u>691 · 29</u> (in inch <u>es) 2 · 0 · · </u>
Ground	lwater Level (+/- 0.01	I foot below top of inner ca	asing, MSL):
	Date/Time	Depth to Groundwater	Groundwater Elevation
Before Purging *After Purging *Before Sampling	3/6/07 3/6/07 5:45	22.6	
C.) WELL PURGING			
Quantity of Water No.of Well Volum Was well pumped	Removed from Well es (based on current l/bailed dry?	(gallons) 0'5 water level) (p	
Equipment used: Bailer type Pump type If not dedica	Disposable ated, method of clear	'Dedicated Ba 'Dedicated Ba ing	
D.) FIELD MEASURE	MENT		
i emperature Equipn pH Equipn Specific Condition	nent Used HACH 7 Z nent Used HACH	COMPANY POCKET	
Comments			

Site Name CITY of Musc	ITINE CED Landh	Permit No	SDP-4-78C
Monitoring Well/Piezometer No.	MW-60	Upgradient/	/
Name of person sampling	RMF	Downgradie <u>nt</u>	
A.) MONITORING WE	LL/PIEZOMETER CONDI	TIONS	
Well/Piezometer Pro If no, explain	operly Capped?	Standing If yes, ex	Water or Litter? No
B.) GROUNDWATER	ELEVATION MEASUREM	IENT (+/- 0.01 foot, MSI	_)
Elevation: Top of i Depth of Well Equipment Used		Ground Elevatile Casing Diameter (in in	ion 714.65 nches) 2.0"
Ground	water Level (+/- 0.01 foot	below top of inner casin	g, MSL):
	Date/Time	Depth to Groundwater	Groundwater Elevation
Before Purging *After Purging *Before Sampling	3/6/06 610pm	44.7 47.0 45.0	
C.) WELL PURGING			
Quantity of Water No.of Well Volum Was well pumped	Removed from Well (galloes (based on current wate //bailed dry?	ons) / r level) /	
Equipment used: Bailer type Pump type If not dedica	Dispossible	'Dedicated Bailer 'Dedicated Bailer	
D.) FIELD MEASURE	MENT		
Temperature Equipn pH Equipn Specific Condition	nent Used HACH COM 7'5 nent Used HACH CO ns 812	_Units NPAMY POCKET FI	PAL TRAL
Comments			
NOTE: Attach Lab groundwa	oratory Report and 8-12" > ater monitoring points. One	t 11" site plan showing le map per sampling rout	ocations of all surface and nd.

Site Name <u>CITY of Musco</u> Monitoring Well/Piezometer No.	_ MW-7		Upgradient Downgradie			
Name of person sampling	RMF	-01816	•			·
A.) MONITORING WE	LL/PIEZOMETE	R CONDIT	ONS			
Well/Piezometer Pro If no, explain	pperly Capped?_	<u>405</u>		Standing W If yes, expl	Vater or Litter? ain —	No
B.) GROUNDWATER	ELEVATION ME	ASUREME	NT (+/- 0.01	foot, MSL)		
Elevation: Top of i Depth of Well Equipment Used	22.25	2ما ما 17 Inside	Ground Casing Dian	nd Elevation	n 714·40 thes) 2·0"	
Ground	water Level (+/- (0.01 foot be	elow top of in	ner casing,	MSL):	
	Date/Time		Depth to Groundwate	er	Groundwater Elevation	٠
Before Purging *After Purging *Before Sampling	3/6/07		<u>21·98</u>	- -		
C.) WELL PURGING			/			
Quantity of Water No.of Well Volume Was well pumped	es (based on cun	Vell (gallon rent water I	s) N/4 evel)			
Equipment used: Bailer type Pump type If not dedica	ted, method of cl			ited Bailer ited Bailer	~! v:	
D.) FIELD MEASURE	MENT					
pH Equipm	s (after stabilizati nent Used HA	CH COMP		KET PAI	ĀL_	
	nent Used HA	CH (o	Units MPANY 1	BOKET	PAL	
Comments		<u></u>				
NOTE: Attach Labo groundwa	oratory Report an iter monitoring po					face and

CITY OF MUSCATINE C&D LANDFILL 70-SDP-4-78C MONITORING WELL SAMPLING RESULTS

SAMPLING DATE: 10/15/2007 U.G.W D.G.W D.G.W D.G.W U.G.W MW 7 MW 2 MW 3 MW 4 MW 6 PARAMETER MCL aug/L 5 $\overline{\mathsf{NT}}$ NT NT NT NT Benzene * 5 NT NT NT NT NT Carbon tetrachloride * NT NT NT NT 0.6 NT 1.4-Dichlorobenzene * NT NT NT NT 5 NT 1,2-Dichloroethane * 7 NT NT NT NT NT 1.1-Dichloroethylene * NT NT $\overline{\mathsf{NT}}$ NT NT 200 1,1,1-Trichloroethane NT NT NT NT 2 $\overline{\mathsf{NT}}$ Vinyl Chloride NT NT NT cis-1,2-Dichloroethylene NT NT 70 NT NT NT NT Tetrachioroethylene * 5 NT NT 5 NT NT $\overline{\mathsf{NT}}$ NT Trichloroethylene * mg/L NT NT NT Arsenic, dissolved 0.05 NT NT NT NT NT NT 2 NT Barium, dissolved NT NT $\overline{\mathsf{NT}}$ NT 0.005 NT Cadmium, dissolved NT NT NT 0.1 NT NT Chromium, dissolved NT NT NT NT 1.3 NT Copper, dissolved NT NT NT NT 5 NT Zinc, dissolved 0.015 NT NT NT NT NT Lead, dissolved NT NT NT Mercury, dissolved 0.002 NT NT NT NT NT NT NT Magnisium, dissolved ___ 0.3 DRY 0.209 2.06 0.183 < 0.100 Iron, dissolved DRY 74 36 58 250 <10 Chloride DRY <1.0 ---1.3 1.4 <1.0 Nitrogen, Ammonia <10 <10 DRY <10 17 Chemical Oxygen Dema < 0.100 DRY <0.100 < 0.100 < 0.100 Phenols ___ < 0.010 DRY < 0.010 0.028 0.023 TOX ___ 7.2 7.4 7.3 DRY 7.5 pН 6.5-8.5

16

1549

17

628

16

763

14

862

DRY

DRY

Temperature, celsius

Conductivity







RECEIVED NOV 1 2 2007

ANALYTICAL REPORT

November 02, 2007

Page 1 of 12

Work Order: 17J0984

Report To

Todd Whipple

Fox Engineering Associates, Inc.

1601 Golden Aspen Drive, Suite 103

Ames, IA 50010

Work Order Information

Date Received: 10/18/2007 9:40AM

Collector: Freeman, Richard

Phone: (515) 233-0000

PO Number:

Project: City of Muscatine C & D Landfill-Fall

Project Number: 6008-06B

Analyte	Result	MRL	Batch	Method	Analyst	Analyzed Qualifier
17J0984-01 MW-2				Matrix:Water	Co	llected: 10/16/07 10:50
Total Organic Halogens (TOX)	<0.010 mg/l	0.010	1J73140	EPA 9020	TVK	11/01/07 14:17
Chloride	<10 mg/l	10	1J72303	USGS I-1184-85	DRB	10/23/07 8:29
Chemical Oxygen Demand	<10 mg/l	10	1J72210	EPA 410.4	SAA	10/22/07 15:16
Nitrogen, Ammonia	1.3 mg/l	1.0	1J72209	SM 4500-NH3 F	SAA	10/22/07 15:14
Phenols, total	<0.100 mg/l	0.100	1J73004	EPA 9065	WAS	10/31/07 15:36
Iron, dissolved	0.209 mg/l	0.100	1J72304	EPA 6010B	RVV	10/24/07 13:52
17J0984-02 MW-3	-			Matrix:Water	Co	llected: 10/16/07 11:00
Total Organic Halogens (TOX)	0.028 mg/l	0.010	1J73141	EPA 9020	TVK	11/01/07 14:20
Chloride	74 mg/l	10	1J72303	USGS I-1184-85	DRB	10/23/07 8:29
Chemical Oxygen Demand	17 mg/l	10	1J72210	EPA 410.4	SAA	10/22/07 15:16
Nitrogen, Ammonia	1.4 mg/l	1.0	1J72209	SM 4500-NH3 F	SAA	10/22/07 15:14
Phenols, total	<0.100 mg/l	0.100	1J73004	EPA 9065	WAS	10/31/07 15:36
Iron, dissolved	2.06 mg/l	0.100	1J72304	EPA 6010B	RVV	10/24/07 13:56
17J0984-03 MW-4				Matrix:Water	Co	llected: 10/16/07 10:35
Total Organic Halogens (TOX)	0.023 mg/l	0.010	1K70127	EPA 9020	TVK	11/01/07 13:37
Chloride	36 mg/l	10	1J72303	USGS I-1184-85	DRB	10/23/07 8:29
Chemical Oxygen Demand	<10 mg/l	10	1J72210	EPA 410.4	SAA	10/22/07 15:16
Nitrogen, Ammonia	<1.0 mg/l	1.0	1J72209	SM 4500-NH3 F	SAA	10/22/07 15:14
Phenols, total	<0.100 mg/l	0.100	1J73004	EPA 9065	WAS	10/31/07 15:36
Iron, dissolved	0.183 mg/l	0.100	1J72304	EPA 6010B	RVV	10/24/07 14:10
17J0984-04 MW-6			-	Matrix:Water	Co	llected: 10/16/07 09:45
Total Organic Halogens (TOX)	<0.010 mg/l	0.010	1K70126	EPA 9020	TVK	11/01/07 13:27
Chloride	58 mg/l	10	1J72303	USGS I-1184-85	DRB	10/23/07 8:29
Chemical Oxygen Demand	<10 mg/l	10	1J72210	EPA 410.4	SAA	10/22/07 15:16
Nitrogen, Ammonia	<1.0 mg/l	1.0	1J72209	SM 4500-NH3 F	SAA	10/22/07 15:14
Phenois, total	<0.100 mg/l	0.100	1J73004	EPA 9065	WAS	10/31/07 15:36
Iron, dissolved	<0.100 mg/l	0.100	1J72304	EPA 6010B	RVV	10/24/07 14:14
The results in this report apply to t		in accordance		iin of custody documer		vtical report must be reprodu







Work Order: 17J0984

November 02, 2007 Page 2 of 12

17J0984-04 MW-6 Matrix: Water Collected: 10/16/07 09:45

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. Samples were preserved in accordance with 40 CFR for pH adjustment unless otherwise noted. MRL= Method Reporting Limit.

Phone 641-792-8451

600 East 17th Street South

Fax 641-792-7989







Work Order: 17J0984

November 02, 2007 Page 3 of 12

Determination of Conventional Chemistry Parameters - Quality Control Keystone Laboratories, Inc. - Newton

Amaluta	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Analyte	Roduit		0							
Batch 16H0220 - 1H60203										
Cal Standard (16H0220-CAL1)				Prepared &	& Analyze	ed: 08/02/0	06			
Phenols, total	-0.00848		mg/l	0.00000						
Cal Standard (16H0220-CAL2)				Prepared &	& Analyze	ed: 08/02/0	06			
Phenols, total	0.0239		mg/i	0.0250800	•	95.2				
Cal Standard (16H0220-CAL3)				Prepared &	& Analyze	ed: 08/02/0	06			
Phenols, total	0.107		mg/l	0.100300		107				
Cal Standard (16H0220-CAL4)				Prepared &	& Analyze	ed: 08/02/0	06			
Phenois, total	0.401		mg/l	0.401200		100				
Cal Standard (16H0220-CAL5)				Prepared &	& Analyze	ed: 08/02/	06			
Phenols, total	1.00		mg/l	1.00300		100				
Cal Standard (16H0220-CAL6)				Prepared &	& Analyze	ed: 08/02/	06			
Phenols, total	2.00		mg/l	2.00600		99.6				
Calibration Check (16H0220-CCV1)				Prepared &	& Analyz	ed: 08/02/	06			
Phenois, total	0.0940		mg/l	0.100000		94.0	90-110			
Batch 17A1613 - 1A71617										
				n . 1	0. 4	-4-01/16/	07			
Cal Standard (17A1613-CAL1)					x Analyz	ed: 01/16/	07			
Chemical Oxygen Demand	-2.35		mg/l	0.00000						
Cal Standard (17A1613-CAL2)				Prepared o	& Analyz	ed: 01/16/	07			
Chemical Oxygen Demand	12.3		mg/l	10.0000		123				







Work Order: 17J0984

November 02, 2007 Page 4 of 12

Determination of Conventional Chemistry Parameters - Quality Control Keystone Laboratories, Inc. - Newton

		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 17A1613 - 1A71617										
Cal Standard (17A1613-CAL3)				Prepared d	& Analyze	d: 01/16/	07			
Chemical Oxygen Demand	21.9		mg/l	20.0000		110				
Cal Standard (17A1613-CAL4)				Prepared &	& Analyze	ed: 01/16/0	07			
Chemical Oxygen Demand	74.0		mg/i	75.0000		98.6				
Cal Standard (17A1613-CAL5)				Prepared a	& Analyze	d: 01/16/0	07			
Chemical Oxygen Demand	97.6		mg/l	100.000		97.6				
Cal Standard (17A1613-CAL6)				Prepared 6	& Analyze	ed: 01/16/	07		· · · · · ·	
Chemical Oxygen Demand	152		mg/l	150.000		101		•		
Batch 17J2203 - 1J72209										
Calibration Check (17J2203-CCV1)				Prepared of	& Analyze	ed: 10/22/	07			
Nitrogen, Ammonia	5.57		mg/l	5.00000		111	80-120			
Calibration Check (17J2203-CCV2)				Prepared	& Analyz	ed: 10/22/	07			
Nitrogen, Ammonia	5.41		mg/l	5.00000		108	80-120			
Initial Cal Check (17J2203-ICV1)				Prepared	& Analyz	ed: 10/22/	07			
Nitrogen, Ammonia	5.26		mg/l	5.00000		105	80-120			
Batch 17J2205 - 1J72211										
Calibration Check (17J2205-CCV1)				Prepared	& Analyz	ed: 10/22/	07			
Chemical Oxygen Demand	77.8		mg/l	75.0000		104	90-110			
• •										







Work Order: 17J0984

November 02, 2007 Page 5 of 12

Determination of Conventional Chemistry Parameters - Quality Control Keystone Laboratories, Inc. - Newton

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 17J2205 - 1J72211										
Calibration Check (17J2205-CCV2)				Prepared &	& Analyze	ed: 10/22/0	7			
Chemical Oxygen Demand	74.6		mg/l	75.0000		99.5	90-110			
Calibration Check (17J2205-CCV3)				Prepared &	& Analyze	ed: 10/22/0	7			
Chemical Oxygen Demand	74.0		mg/l	75.0000		98.6	90-110			
Calibration Check (17J2205-CCV4)			<u></u>	Prepared &	& Analyze	ed: 10/22/0	7			
Chemical Oxygen Demand	73.6		mg/l	75.0000		98.2	90-110			
Batch 17J3002 - 1J73004										
Calibration Check (17J3002-CCV1)					10/30/07	Analyzed:				
Phenols, total	0.0886		mg/l	0.100300		88.3	80-120			
Initial Cal Blank (17J3002-ICB1)				Prepared:	10/30/07	Analyzed:	10/31/07			
Phenols, total	-0.00848		mg/l							
Initial Cal Check (17J3002-ICV1)				Prepared:	10/30/07	Analyzed:	10/31/07			
Phenols, total	0.0913		mg/l	0.100300		91.0	80-120			
Batch 1J72209 - Wet Chem Prepara	ition								-	
Blank (1J72209-BLK1)				Prepared &	& Analyz	ed: 10/22/0	17			
Nitrogen, Ammonia	ND	1.0	mg/l							
Matrix Spike (1J72209-MS1)		Source: 17J09				ed: 10/22/0				
Nitrogen, Ammonia	5.39	1.0	mg/l	5.00000	ND	108	64-129			







Work Order: 17J0984

November 02, 2007 Page 6 of 12

Determination of Conventional Chemistry Parameters - Quality Control Keystone Laboratories, Inc. - Newton

		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 1J72209 - Wet Chem Preparation										
Matrix Spike Dup (1J72209-MSD1)	So	ource: 17J0985	-16	Prepared &	د Analyze	d: 10/22/0)7			
Nitrogen, Ammonia	5.22	1.0	mg/l	5.00000	ND	104	64-129	3.20	12	
Batch 1J72210 - Wet Chem Preparation										
Blank (1J72210-BLK1)				Prepared &	₹ Analyze	d: 10/22/0)7			
Chemical Oxygen Demand	ND	10	mg/l							
LCS (1J72210-BS1)				Prepared &	ኒ Analyze	d: 10/22/0)7			.,,
Chemical Oxygen Demand	75.9	10	mg/l	75.0000		101	78-117			
Matrix Spike (1J72210-MS1)	S	ource: 17J0985	-09	Prepared &	₹ Analyze	d: 10/22/0)7			
Chemical Oxygen Demand	49.5	10	mg/l	42.8571	5.95	102	60-139			
Matrix Spike Dup (1J72210-MSD1)	S	ource: 17J0985	-09	Prepared &	& Analyze	d: 10/22/0	07			
Chemical Oxygen Demand	50.2	10	mg/l	42.8571	5.95	103	60-139	1.46	26	
Batch 1J72303 - Wet Chem Preparation										
Blank (1J72303-BLK1)				Prepared &	& Analyze	:d: 10/23/0	07			
Chloride	ND	10	mg/l							
Matrix Spike (1J72303-MS1)	S	ource: 17J0984	1-03	Prepared &	& Analyze	:d: 10/23/0	07			
Chloride	58.2	10	mg/l	25.0000	36.2	88.0	75-116			
Matrix Spike Dup (1J72303-MSD1)	s	ource: 17J0984	1-03	Prepared &	& Analyze	d: 10/23/0	07			
Chloride	58.7	10	mg/l	25.0000	36.2	90.0	75-116	0.855	10	







Work Order: 17J0984

November 02, 2007 Page 7 of 12

Determination of Conventional Chemistry Parameters - Quality Control Keystone Laboratories, Inc. - Newton

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 1J72303 - Wet Chem Preparati	ion									
Reference (1J72303-SRM1)				Prepared	& Analyz	ed: 10/23/0	7			
Chloride	21.0	10	mg/l	20.0000		105	90-110			
Batch 1J73004 - Wet Chem Preparat	ion				<u>-</u>					
Blank (1J73004-BLK1)			.,	Prepared:	10/30/07	Analyzed:	10/31/07			
Phenols, total	ND	0.100	mg/l							
LCS (1J73004-BS1)				Prepared:	10/30/07	Analyzed:	10/31/07			
Phenols, total	0.0832	0.100	mg/l	0.100300		83.0	60-125			
Duplicate (1J73004-DUP1)	So	ource: 17J098	4-03	Prepared:	10/30/07	Analyzed:	10/31/07			
Phenols, total	ND	0.100	mg/l		ND	•			20	
Matrix Spike (1J73004-MS1)	So	ource: 17J098	4-04	Prepared:	10/30/07	Analyzed:	10/31/07			
Phenols, total	0.0940	0.100	mg/l	0.100300	ND	93.7	60-140			
Batch 1J73140 - TOX/TX/EOX										
Blank (1J73140-BLK1)				Prepared	& Analyz	ed: 10/31/0	17			
Total Organic Halogens (TOX)	ND	0.010	mg/l							
LCS (1J73140-BS1)				Prepared	& Analyz	ed: 10/31/0)7			
Total Organic Halogens (TOX)	0.0918	0.010	mg/l	0.103000		89.1	73-126			
Reference (1J73140-SRM1)				Prepared	& Analyz	ed: 10/31/0)7			
Total Organic Halogens (TOX)	0.0989	0.010	mg/l	0.103000		96.0	90-110			







Work Order: 17J0984

November 02, 2007 Page 8 of 12

Determination of Conventional Chemistry Parameters - Quality Control Keystone Laboratories, Inc. - Newton

		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 1J73141 - TOX/TX/EOX										
Blank (1J73141-BLK1)				Prepared of	& Analyze	ed: 10/31/	07			
Total Organic Halogens (TOX)	ND	0.010	mg/i							
LCS (1J73141-BS1)				Prepared	& Analyze	ed: 10/31/	07	-,		
Total Organic Halogens (TOX)	0.0982	0.010	mg/l	0.103000		95.3	73-126			
Reference (1J73141-SRM1)				Prepared of	& Analyze	ed: 10/31/	07			
Total Organic Halogens (TOX)	0.1026	0.010	mg/l	0.103000		99.7	90-110			
Batch 1K70126 - TOX/TX/EOX										
Blank (1K70126-BLK1)				Prepared	& Analyz	ed: 11/01/	07			
Total Organic Halogens (TOX)	ND	0.010	mg/l							
LCS (1K70126-BS1)				Prepared	& Analyz	ed: 11/ <u>01/</u>	07			
Total Organic Halogens (TOX)	0.0993	0.010	mg/l	0.103000		96.4	73-126			
Reference (1K70126-SRM1)				Prepared	& Analyz	ed: 11/01/	07			
Total Organic Halogens (TOX)	0.0993	0.010	mg/l	0.103000		96.4	90-110			
Reference (1K70126-SRM2)				Prepared:	11/01/07	Analyzed	i: 11/02/07	7		
Total Organic Halogens (TOX)	0.1003	0.010	mg/l	0.103000		97.4	90-110			
Batch 1K70127 - TOX/TX/EOX										
Blank (1K70127-BLK1)				Prepared	& Analyz	ed: 11/01/	07			
Total Organic Halogens (TOX)	ND	0.010	mg/l							







Work Order: 17J0984

November 02, 2007 Page 9 of 12

Determination of Conventional Chemistry Parameters - Quality Control Keystone Laboratories, Inc. - Newton

		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 1K70127 - TOX/TX/EOX								·-···		
LCS (1K70127-BS1)				Prepared	& Analyze	ed: 11/01/	07			
Total Organic Halogens (TOX)	0.1081	0.010	mg/l	0.103000		105	73-126			
Reference (1K70127-SRM1)				Prepared	& Analyze	ed: 11/01/	07		·	
Total Organic Halogens (TOX)	0.1034	0.010	mg/l	0.103000		100	90-110			
Reference (1K70127-SRM2)				Prepared:	11/01/07	Analyzed	l: 11/02/07			
Total Organic Halogens (TOX)	0.1054	0.010	mg/l	0.103000		102	90-110			

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. Samples were preserved in accordance with 40 CFR for pH adjustment unless otherwise noted. MRL= Method Reporting Limit.

Phone 641-792-8451

600 East 17th Street South

Fax 641-792-7989







Work Order: 17J0984

November 02, 2007 Page 10 of 12

Determination of Dissolved Metals - Quality Control Keystone Laboratories, Inc. - Newton

		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch 17J2404 - 1J72304										
Calibration Blank (17J2404-CCB1)				Prepared d	& Analyze	d: 10/24/0	07			
Iron, dissolved	0.00270		mg/l	0.00000						
Calibration Blank (17J2404-CCB2)				Prepared d	& Analyze	d: 10/24/0	07			
Iron, dissolved	0.00570		mg/l	0.00000						
Calibration Blank (17J2404-CCB3)				Prepared of	& Analyze	ed: 10/24/0	07			
Iron, dissolved	-0.0100		mg/l	0.00000						
Calibration Check (17J2404-CCV1)				Prepared of	& Analyze	ed: 10/24/0	07			
Iron, dissolved	21.5		mg/l	21.0000		102	90-110			
Calibration Check (17J2404-CCV2)				Prepared of	& Analyze	d: 10/24/	07			
Iron, dissolved	21.4		mg/l	21.0000		102	90-110			
Calibration Check (17J2404-CCV3)			•	Prepared a	& Analyze	ed: 10/24/	07			
Iron, dissolved	21.1		mg/l	21.0000		100	90-110			
High Cal Check (17J2404-HCV2)				Prepared	& Analyz	ed: 10/24/	07			
Iron, dissolved	21.5		mg/l	20.0000		108	90-110			
Initial Cal Blank (17J2404-ICB1)				Prepared	& Analyz	ed: 10/24/	07			
Iron, dissolved	0.0158	····	mg/l	0.00000						
Initial Cal Check (17J2404-ICV1)				Prepared	& Analyz	ed: 10/24/	07			
Iron, dissolved	21.7		mg/l	21.0000		103	90-110			
Secondary Cal Check (17J2404-SCV1)				Prepared	& Analyz	ed: 10/24/	07			
Iron, dissolved	2.64		mg/l	2.50000		106	90-110			







Work Order: 17J0984

November 02, 2007 Page 11 of 12

Determination of Dissolved Metals - Quality Control Keystone Laboratories, Inc. - Newton

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 1J72304 - Dissolved Metal Prep										
Blank (1J72304-BLK1)				Prepared:	10/23/07	Analyzed:	10/24/07			
Iron, dissolved	ND	0.100	mg/l							
Matrix Spike (1J72304-MS1)	Se	ource: 17J081	2-06	Prepared:	10/23/07	Analyzed:	10/24/07			
Iron, dissolved	0.382	0.100	mg/l	0.200000	0.164	109	79-135			
Matrix Spike Dup (1J72304-MSD1)	Se	ource: 17J081	2-06	Prepared:	10/23/07	Analyzed:	10/24/07			
Iron, dissolved	0.376	0.100	mg/l	0.200000	0.164	106	79-135	1.64	11	

ND = Non Detect; REC= Recovery; RPD= Relative Percent Difference

Certified Analyses included in this Report

Method/Mat	trix A	nalyte		Certifications
EPA 410.4 in	Water			
	С	hemical Oxygen D	emand	IA-NT,KS-NT,NELAC
EPA 6010B ii	n Water			
	lr	on, dissolved		IA-NT,KS-NT,NELAC
EPA 9020 in	Water			
	т	otal Organic Halog	ens (TOX)	IA-NT,NELAC
EPA 9065 in	Water			
	Р	henols, total		IA-NT,KS-NT,NELAC
SM 4500-NH	3 F in Water			
	N	litrogen, Ammonia		IA-NT
USGS I-1184	1-85 in Water			
	C	hloride		IA-NT
Code	Description		Number	Expires
IA-NT	Iowa Department of Natural Resource	es	095	02/01/2008
KS-NT	Kansas Department of Health and E	nvironment	E-10287	07/31/2008
NELAC	New Jersey Department of Environm	nental Protection	IA001	06/30/2008







Work Order: 17J0984

November 02, 2007 Page 12 of 12

End of Report

Keystone Laboratories, Inc.

Sue Thompson Project Manager I

CHAIN OF CUSTODY

PRINT OR TYPE INFORMATION BELOW CITY/ST/ZIP: ADDRESS: SITE NAME: SAMPLER: PHONE: LABORATORIES, INC. 000 600 E. 17th St. S. Phone: 641-792-8451 Fax: 641-792-7989 Newton, IA 50208 FAX: COMPANY NAME:... PHONE: CITY/ST/ZIP: ADDRESS: NAME: REPORT TO: 3012 Ansborough Ave. Phone: 319-235-4440 Fax: 319-235-2480 Waterloo, IA 50701 ☐ 1304 Adams Kansas City, KS 66103 Phone: 913-321-7856 NAME:_ ADDRESS: 1000 5 COMPANY NAME: Co Xu G Keystone Quote No.: PHONE: SOS CITY/ST/ZIP/MISKA BILL TO: 913-321-7937 Louro 1809015 PAGE_ (If Applicable) Musia tisk 689 유

FOHM: CCH /-9/		Pink - Sampler Copy	ODV.	Vellow - I ah Conv	<u>حالم</u> >	Link Danor	Osision Bota			
			04.6	Time (John Charles		Time		
	-	Remarks:	18-07	Date C		Received for Lab by: (Signature)		Date		Relinquished by: (Signature)
Contact Lab Prior to Submission		Candada		Time			3	Time 40 Ar		Kork Exico
	☐ Rush	Turn-Around:		Date		(Signature)	Peceived by: (Signature)	Date // 8/	ŀ	Relinquished by: (Signature)
				\vdash						
					-	-				
			•							
120			2			6		945-Am	\	minde
20						4	_	1035AM		mw 4
70						8		11 Am		MW 3
			メント	×	2	1/2	making au	7,050 M	10/Lelo	m x
NTS	SAMPLE CONDITION/COMMENTS						SAMPLE LOCATION	TIM	DAT	CLIENT SAMPLE NUMBER
SAMPLE	°C		- '.Q	AB/C	OF C			E	E	
	SAMPLE TEMPERATURE UPON RECEIPT:		, 1	OMPC	CONT					
784	1750984			SITE	AINE					
WORK ORDER NO.	LABORATORY WORK ORDER NO.	ANALYSES REQUIRED	AN		RS 					
				$\left\{ \left[\right] \right\}$						

Original - Return with Report

Yellow - Lab Copy

Pink - Sampler Copy

Nonitoring Well/Piezometer No.	MW-2		Upgradient Downgradie	nt		
Name of person sampling		. '	Downgradie	ant V	<u> </u>	
•		COMPITI	ONC			
A.) MONITORING WE	LL/PIEZOMETE	CONDITIO	JNS			
Well/Piezometer Pro If no, explain	operly Capped?_	<u>405</u>		Standing V If yes, expl	Vater or Litter? Nain	
B.) GROUNDWATER	ELEVATION ME	ASUREME	NT (+/- 0.01	foot, MSL)		
Elevation: Top of Depth of Well Equipment Used	inner well casing 42.16 SOLINST	<u>640 · 86</u> Inside (Groui Casing Dian	nd Elevatio neter (in ind		
Ground	water Level (+/-0	0.01 foot be	low top of in	ner casing,	MSL):	
	Date/Time		Depth to Groundwate	er	Groundwater Elevation	
Before Purging *After Purging *Before Sampling	1 <u>0 15 07</u> 1 <u>0 16 07 10</u> 5	Dame .	7:6 28:5 8:0	• •		
C.) WELL PURGING						
Quantity of Water No.of Well Volum Was well pumped	es (based on cun	ent water le				
Equipment used: Bailer type Pump type If not dedica	Disposable			ited Bailer ited Bailer		
D.) FIELD MEASURE	MENT					
pH Equipn Specific Condition	s (after stabilizati 17 nent Used HA 15 nent Used HA	on): CH COMPI		KET PA	L AL PAL	
Comments			·			
NOTE: Attach Lab		d 8-12" x 1	1" site plan :	showing lo	cations of all surfac	e and

Monitoring Well/Piezometer No.	MW-3	Upgradient Downgradient	
lame of person sampling		Downgradie <u>nt</u>	
A.) MONITORING WE	ELUPIEZOMETER C	ONDITIONS	
•			:
Well/Piezometer Pr If no, exp <u>lain</u>	operly Capped?		ing Water or Litter? No explain
B.) GROUNDWATER	ELEVATION MEASU	JPEMENT (+/- 0.01 foot, I	MSL)
Elevation: Top of Depth of Well Equipment Used	inner well casing & 22.0(e SOLINST	40·3 (Ground Ele Inside Casing Diameter (vation 638.30 in inches) 2.0"
Ground	dwater Level (+/- 0.01	foot below top of inner ca	asing, MSL):
	Date/Time	Depth to Groundwater	Groundwater Elevation
Before Purging *After Purging *Before Sampling	10/15/07 11:00	11·3 20:3 11·3	
C.) WELL PURGING			
Quantity of Wate No.of Well Volun Was well pumpe	r Removed from Well nes (based on current d/bailed dry?	(gallons) † water level) Z YeG	
Equipment used: Bailer type Pump type If not dedic	Digagable pol	Dedicated Ba	
D.) FIELD MEASURE	EMENT		
Temperature Equip pH Equip Specific Conditio	ats (after stabilization):	Units Company POCKET Company POCKET Units Company POCKE	PAL T PAL CET PAL
Comments			

Monitoring Well/Piezometer No.	MW-4	Upgradient Downgradie			
Name of person sampling			311		•
A.) MONITORING WE	ELL/PIEZOMETER	CONDITIONS			
Well/Piezometer Pr If no, explain	operly Capped?	<u>405</u>	Standing W	/ater or Litter?	№
B.) GROUNDWATER	ELEVATION MEA	SUREMENT (+/- 0.01	foot, MSL)		
Elevation: Top of Depth of Well Equipment Used	inner well casing 24.43 SOUMST	(93·22 Grou Inside Casing Dian		n (91.29 hes) 2.0"	
Ground	dwater Level (+/- 0.	01 foot below top of ir	nner casing,	MSL):	
	Date/Time	Depth to Groundwat	er	Groundwater Elevation	
Before Purging *After Purging *Before Sampling	10/15/1007	21.55 2437.0 21.6	- - -		
C.) WELL PURGING	·				
Quantity of Water No.of Well Volum Was well pumper	r Removed from Water (based on curred/bailed dry?	ell (gallons) 0'5 ent water level) /			
Equipment used: Bailer type Pump type ff not dedica	Disposable.	'Dedica	ated Bailer ated Bailer		
D.) FIELD MEASURE	MENT				
Temperature Equipr pH Equipr Specific Conditio	ts (after stabilization) ment Used HAC ment Used HAC	n): Units H_Compary Pox	EXET PAI BOXET F	AL TAL	
Comments					
NOTE: Attach Lab groundw	poratory Report and rater monitoring poi	l 8-12" x 11" site plan nts. One map per san	showing loc npling round	ations of all surf	face and


Monitoring Well/Piezometer No.	MW-C		Jpgradient _ Downgradie			
Name of person sampling	<u> </u>		John gradio			
A.) MONITORING WE	LL/PIEZOMETE	R CONDITIO	NS			
Well/Piezometer Pr If no, explain	operly Capped?_	<u>405</u>		Standing V If yes, expl	Vater or Litter?	N₀
B.) GROUNDWATER	ELEVATION ME	ASUREMEN	IT (+/- 0.01	foot, MSL)		
Elevation: Top of Depth of Well Equipment Used	<u>48.98</u>	716.63 Inside (Grour Casing Diam		n 7/4·65 hes) 2·0"	
Ground	lwater Level (+/- (0.01 foot bel	ow top of in	ner casing,	, MSL):	
	Date/Time		Depth to Sroundwate	er	Groundwater Elevation	•
Before Purging *After Purging *Before Sampling	10/15/07 10/16/07 9/4	- 15 -	47.0			
C.) WELL PURGING	'					
Quantity of Water No.of Well Volum Was well pumped	es (based on cun					
Equipment used: Bailer type Pump type If not dedica	Disposable ated, method of cl	eaning		ted Bailer ted Bailer		
D.) FIELD MEASURE	MENT					
pH Equipr Specific Conditio	ts (after stabilizati 14 nent Used HA 7.3 nent Used HA	bn): CH COMPA		KET PA	L AL TAL	
Comments						
NOTE: Attach Lab groundw	oratory Report ar ater monitoring po	nd 8-12" x 11 pints. One m	" site plan s ap per sam	showing loo pling round	cations of all surfa	ace and

Site Name CITY of Musc	ATINE CED	Landfill Permit N	lo. <u>70-</u>	SDP-4-78	
Monitoring Well/Piezometer No.		Upgradie Downgra	ent /		
Name of person sampling		Downgra	adient	·	
A.) MONITORING WE	LL/PIEZOMETER	CONDITIONS			
Well/Piezometer Pro	operly Capped?	UPS	Standing \	Water or Litter?	ے م
If no, explain			If yes, exp		
B.) GROUNDWATER	ELEVATION MEA	ASUREMENT (+/- 0	.01 foot, MSL)	
Elevation: Top of i Depth of Well Equipment Used	<u>22.25</u>	716.65 G Inside Casing D	round Elevation Diameter (in in	on 714·40 ches) 2·0"	
Ground	lwater Level (+/- 0	.01 foot below top o	of inner casing	j, MSL):	
	Date/Time	Depth to Groundy		Groundwater Elevation	
Before Purging *After Purging *Before Sampling	10/15/07	<u>21.89</u> 			
C.) WELL PURGING			/.		
Quantity of Water No.of Well Volum Was well pumped	es (based on curr	/ell (gallons) ~ / ent water level) /	/4		
Equipment used: Bailer type Pump type If not dedica	ated, method of cle	'Dec	dicated Bailer dicated Bailer		
D.) FIELD MEASURE	MENT				
Weather Conditior Field Measurment Temperature	s (after stabilization	on): Units			
		H COMPANY 7	BCKET PA	<u>L</u>	
Equipn Specific Condition	nent Used HA	CH COMPANY Units CH COMPANY	POCKET D	PAL TAL	
• •		•			
NOTE: Attach Lab	oratory Report and	d 8-12" x 11" site pl ints. One map per s	an showing lo sampling roun	cations of all surfaced.	ce and

ATTACHMENT D

Concentration versus Time Graphs


				U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL	Mean + 2STD	MW 6	MW 2	MW 3	MW 4	MW 7
		mg/L						
04/15/95	Iron, dissolved	0.3	5.215	0.41	0.25	12.3	0.27	0.11
07/15/95	Iron, dissolved	0.3	5.215	0.02	0.18	7.94	0.05	0.01
10/15/95	Iron, dissolved	. 0.3	5.215	0.21	0.54	7.31	0.25	0.29
01/15/96	Iron, dissolved	0.3	5.215	0.74	0.59	6.41	0.06	0.81
04/15/96	Iron, dissolved	0.3	5.215	0.33	0.12	10.05	, 0.3	0.76
10/15/96	Iron, dissolved	0.3	5.215	0.07	1.16	6.33	0.09	0.31
04/15/97	Iron, dissolved	0.3	5.215	0.04	0.69	19.32	0.12	0.15
10/15/97	Iron, dissolved	0.3	5.215	0.015	0.54	15.1	0.015	dry
04/15/98	Iron, dissolved	0.3	5.215	0.1	0.6	21	0.1	0.1
10/15/98	Iron, dissolved	0.3	5.215	10.8	0.661	13.5	0.914	14.9
04/15/99	Iron, dissolved	0.3	5.215	0.0022	0.046	1.19	0.0022	0.0022
10/15/99	Iron, dissolved	0.3	5.215	0.413	0.0022	0.412	0.0022	0.0022
04/15/2000	Iron, dissolved	0.3	5.215	0.0022	0.583	11.7	0.0022	0.0022
10/15/2000	Iron, dissolved	0.3	5.215	0.008	0.653	7.4	0.014	0.0022
04/15/2001	Iron, dissolved	0.3	5.215	0.19	3.5	9.9	0.16	0.11
10/15/2001	Iron, dissolved	0.3	5.215	0.05	0.95	8.4	0.05	0.05
04/15/2002	Iron, dissolved	0.3	5.215	0.06	0.6	0.06	0.06	0.06
10/15/2002	Iron, dissolved	0.3	5.215	0.27	1	5.3	0.16	dry
03/13/2003	Iron, dissolved	0.3	5.215	<0.3	0.511	4.78	0.215	dry
09/04/2003	Iron, dissolved	0.3	5.215	<0.3	0.305	1.06	<0.3	dry
03/03/2004	Iron, dissolved	0.3	5.215	<0.30	0.466	3.38	0.018	dry
09/08/2004	Iron, dissolved	0.3	5.215	<0.3	0.305	1.06	<0.3	dry
03/10/2005	Iron, dissolved	0.3	5.215	0.095	0.441	5.09	1.85	dry
09/08/2005	Iron, dissolved	0.3	5.215	<0.3	0.4	0.638	<0.3	dry
03/15/2006	Iron, dissolved	0.3	5.215	0.073	0.799	9.01	<0.030	dry
09/27/2006	Iron, dissolved	0.3	5.215	<0.030	0.371	1.69	dry	dry
03/06/2007	Iron, dissolved	0.3	5.215	0.194	0.460	2.85	0.966	dry
10/15/2007	Iron, dissolved	0.3	5.215	<0.100	0.209	2.06	0.183	dry
	Mean			0.671067	0.604721	6.972857	0.254417	1.1043
	Standard Deviation (STI	D)		2.272052	0.619649	5.549156	0.422419	3.570497
	Mean + 2STD			5.21517	1.844019	18.07117	1.099256	8.245294




GROUNDWATER SYSTEM MUSCATINE C & D LANDFILL 70-SDP-4-78C CONCENTRATION VERSUS TIME

				U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL	Mean + 2STD	MW 6	MW 2	MW 3	MW 4	MW 7
		mg/L						
04/15/95	Chloride	250	101.862	32.5	1.8	202.5	37	2.4
07/15/95	Chloride	250	101.862	42.6	1.8	245.1	24.8	6.5
10/15/95	Chloride	250	101.862	51.1	1.7	177.5	59.8	6.6
01/15/96	Chloride	250	101.862	85.1	2.3	303.7	87.5	6.8
04/15/96	Chloride	250	101.862	62.5	2.3	190	108.2	7.2
	Chloride	250	101.862	49.6	2.5	169.8	62.3	6.4
04/15/97	Chloride	250	101.862	58.9	0.5	160.4	112.3	10.3
10/15/97	Chloride	250	101.862	72	8	200	69	dry
04/15/98	Chloride	250	101.862	120	13	450	150	28
10/15/98	Chloride	250	101.862	60.1	21.8	273	54.6	21.8
04/15/99	Chloride	250	101.862	69.2	0.5	54.3	90.5	12.4
10/15/99	Chloride	250	101.862	64.7	10.5	195	91.1	6.2
04/15/2000	Chloride	250	101.862	55.8	0.5	204	103	12.4
10/15/2000	Chloride	250	101.862	39	0.5	133	67.4	3.37
04/15/2001	Chloride	250	101.862	46.8	2.5	196	118	6.8
10/15/2001	Chloride	250	101_862	66.3	2.5	164	53.1	7
04/15/2002	Chloride	250	101.862	48	0.5	139	51	5
10/15/2002	Chloride	250	101.862	64	1.4	110	46	dry
03/13/2003	Chloride	250	101.862	90	<10	116	50	dry
09/04/2003	Chloride	250	101.862	86	<10	108	42	dry
03/03/2004	Chloride	250	101.862	84	<10	85	61	dry
09/08/2004	Chloride	250	101.862	86	<10	108	42	dry
03/10/2005	Chloride	250	101.862	81	<10	91	30	dry
09/08/2005	Chloride	250	101.862	72	<10	57	43	dry
03/15/2006	Chloride	250	101.862	62	<10	91	30	dry
09/27/2006	Chloride	250	101.862	69	<10	59	dry	dry
03/06/2007	Chloride	250	101.862	62	<10	64	52	dry
10/15/2007	Chloride	250	101.862	58	<10	74	36	dry

65.65 4.144444 157.8679 65.61481 9.323125 Mean Standard Deviation (STD) 18.10617 5.533858 86.3073 30.98084 6.53245 Mean + 2STD 330.4825 127.5765 22.38802 101.8623 15.21216




				U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL	Mean + 2STD	MW 6	MW 2	MW 3	MW 4	MW 7
0.445405	A	mg/L	2.506	0.96	1 56	1.47	0.53	0.72
	Nitrogen, Ammonia		3.596	0.86	1.56			
	Nitrogen, Ammonia		3.596	6.7	2.19	6.7	1.91	1.42
	Nitrogen, Ammonia		3.596	0.47	1.38	2.06	0.47	2.94
	Nitrogen, Ammonia		3.596	0.56	1.62	1.56	0.51	0.78
	Nitrogen, Ammonia		3.596	0.1	1.25	1.18	0.1	80.0
	Nitrogen, Ammonia		3.596	0.06	1.17	1.31	0.025	0.06
	Nitrogen, Ammonia		3.596	0.06	1.22	1.25	0.06	0.06
	Nitrogen, Ammonia		3.596	0.09	1.17	1.13	0.18	dry
04/15/98	Nitrogen, Ammonia		3.596	0.05	2.4	2.8	0.05	0.05
10/15/98	Nitrogen, Ammonia		3.596	0.025	1.29	1.18	0.108	0.067
04/15/99	Nitrogen, Ammonia		3.596	0.25	1.2	1.19	0.25	0.25
10/15/99	Nitrogen, Ammonia		3.596	0.65	2.2	2.05	0.65	0.65
	Nitrogen, Ammonia		3.596	0.448	0.336	0.448	0.025	0.025
10/15/2000	Nitrogen, Ammonia		3.596	0.025	0.4	0.6	0.025	1
04/15/2001	Nitrogen, Ammonia		3.596	0.1	1	1.02	0.1	0.1
10/15/2001	Nitrogen, Ammonia		3.596	0.1	1.2	1.48	0.1	0.1
04/15/2002	Nitrogen, Ammonia		3.596	0.11	0.46	1.3	0.1	0.254
10/15/2002	Nitrogen, Ammonia		3.596	0.025	1.2	1.4	0.13	dry
03/13/2003	Nitrogen, Ammonia		3.596	<1	1.1	1.1	<1	dry
09/04/2003	Nitrogen, Ammonia		3.596	<1	1.4	1.2	<1	dry
03/03/2004	Nitrogen, Ammonia		3.596	<1.0	<1.0	<1.0	<1.0	dry
09/08/2004	Nitrogen, Ammonia		3.596	<1.0	<1.0	1.2	<1.0	dry
03/10/2005	Nitrogen, Ammonia		3.596	<1.0	1.2	1.3	<1.0	dry
09/08/2005	Nitrogen, Ammonia		3.596	<1.0	<1.0	<1.0	<1.0	dry
03/15/2006	Nitrogen, Ammonia		3.596	<1.0	1.5	3.1	<1.0	dry
09/27/2006	Nitrogen, Ammonia		3.596	<1.0	1.4	1.2	dry	dry
03/06/2007	Nitrogen, Ammonia		3.596	<1.0	1.2	1.7	<1.0	dry
	Nitrogen, Ammonia		3.596	<1.0	1.3	1.4	<1.0	dry
	•							
				0.5005	. 4 00004	4.000	0.005700	0.50475
	Mean			0.5935	1.29384	1.628	0.295722	0.53475
	Standard Deviation (ST	ט)		1.501318	0.478132	1.155897	0.436515	0.741713
	Mean + 2STD			3.596137	2.250103	3.939793	1.168751	2.018176




GROUNDWATER SYSTEM MUSCATINE C & D LANDFILL 70-SDP-4-78C CONCENTRATION VERSUS TIME

			March COTD	U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL mg/L	Mean + 2STD	MVV 6	MW 2	MW 3	MW 4	MW 7
04/15/95			208.653	2.9	0.05	42	74	4.3
07/15/95			208.653	62	42	31	63	2.8
10/15/95			208.653	63	42	42	31	5.1
01/15/96			208.653	165	31	130	63	63
04/15/96			208.653	188	74	188	74	53
10/15/96			208.653	31	21	290	63	21
04/15/97			208.653	31	10	97	42	42
10/15/97			208.653	2.5	2.5	82	31	dry
04/15/98			208.653	2.5	2.5	31	25	8
10/15/98			208.653	2	16	47	25	2
04/15/99			208.653	10	10	31	29	10
10/15/99			208.653	293	585	191	252	170
04/15/2000			208.653	84.1	53.1	162	120	44.3
10/15/2000	COD		208.653	57.5	53.1	164	44.3	90.7
04/15/2001			208.653	2.5	2.5	32	14	2.5
10/15/2001			208.653	2.5	2.5	30	14	2.5
04/15/2002			208.653	23.8	NT	107	25.9	43.4
10/15/2002	COD		208.653	3	3	20	10	dry
03/13/2003	COD		208.653	<10	<10	20	12	dry
09/04/2003	COD		208.653	<10	<10	28	16	dry
03/03/2004	COD		208.653	<10	<10	25	18	dry
09/08/2004	COD		208.653	<10	11	24	12	dry
03/10/2005			208.653	<10	<10	26	<10	dry
09/08/2005			208.653	<10	<10	18	<10	dry
03/15/2006			208.653	22	<10	53	<10	dry
09/27/2006			208.653	<10	<10	29	dry	dry
03/06/2007			208.653	<10	<10	27	20	dry
10/15/2007	COD		208.653	<10	<10	17	<10	dry
	Mean			55.17368	53.40278	70.85714	46.87826	35.2875
	Standard Deviation (STD)}		76.73959	130.7134	68.65114	51.24076	43.49214
		,					- ·· - · · · ·	
	Mean + 2STD			208.6529	314.8295	208.1594	149.3598	122.2718




GROUNDWATER SYSTEM MUSCATINE C & D LANDFILL 70-SDP-4-78C CONCENTRATION VERSUS TIME

				U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL	Mean + 2STD	MW 6	MW 2	MW 3	MW 4	MW 7
	1	ng/L						
10/15/95			0.086	0.05	0.05	0.05	0.05	0.05
10/15/96	TOX		0.086	0.1	0.1	0.1	0.1	0.1
10/15/97	TOX		0.086	0.007	0.0025	0.026	0.007	0.0001
10/15/98	TOX		0.086	0.011	0.0025	0.019	0.945	0.01
10/15/99	TOX		0.086	0.001	0.001	0.001	0.001	0.001
10/15/2000	TOX		0.086	0.05	0.05	0.05	0.05	0.05
10/15/2001	TOX		0.086	0.005	0.005	0.018	0.024	0.005
10/15/2002	TOX		0.086	0.011	0.0025	0.029	0.031	dry
09/04/2003	TOX		0.086	<0.01	<0.01	0.018	0.014	dry
09/08/2004	TOX		0.086	0.018	<0.010	0.032	0.021	dry
09/08/2005	TOX		0.086	<0.010	<0.010	0.014	0.034	dry
09/27/2006	TOX		0.086	0.01	0.037	<0.010	dry	dry
10/15/2007	TOX		0.086	<0.010	<0.010	0.028	0.023	dry
	Mean			0.0263	0.027833	0.032083	0.108333	0.030871
	Standard Deviation (STD)		0.029705	0.032389	0.024459	0.253492	0.034754
	Mean + 2STD			0.085711	0.092612	0.081001	0.615318	0.100379



GROUNDWATER SYSTEM MUSCATINE C & D LANDFILL 70-SDP-4-78C CONCENTRATION VERSUS TIME

				U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL	Mean + 2STD	MW 6	MW 2	MW 3	MW 4	MW 7
	i	mg/L						
10/15/95	Phenois		0.024	0.005	0.005	0.005	0.005	0.005
10/15/96	Phenois		0.024	0.01	0.01	0.01	0.01	0.01
10/15/97	PhenoIs		0.024	0.016	0.018	0.018	0.016	dry
10/15/98	Phenols		0.024	0.025	0.025	0.025	0.025	0.025
10/15/99	Phenois		0.024	0.0025	0.0025	0.0025	0.0025	0.0025
10/15/2000	Phenois		0.024	0.0025	0.0318	0.0025	0.0025	0.0025
10/15/2001	Phenois		0.024	0.01	0.01	0.01	0.01	0:01
10/15/2002	Phenols		0.024	0.0025	0.0025	0.0025	0.0025	dry
09/04/2003	Phenols		0.024	<0.1	<0.1	<0.1	<0.1	dry
09/08/2004	Phenois	***	0.024	<0.100	<0.100	<0.100	<0.100	dry
09/08/2005	Phenois		0.024	<0.100	<0.100	<0.100	<0.100	dry
09/27/2006	Phenols		0.024	<0.100	<0.100	<0.100	dry	dry
10/15/2007	Phenols		0.024	<0.100	<0.100	<0.100	<0.100	dry
	Mean			0.009188	0.0131	0.009438	0.009188	0.009167
	Standard Deviation (STD)		0.007496	0.010154	0.007748	0.007496	0.007728
	Mean + 2STD			0.024179	0.033408	0.024933	0.024179	0.024623



ATTACHMENT E

Water Elevation Data

Water Level Data Muscatine C&D Landfill

Well/TOC	MW-1	640.42	MW-2	640.86	MW-3	640.36	MW-4	693.22	MW-5	716.8	MW-6	716.63	MW-7	716.65	PZ-8	692.99
Depth of Well		67.09		42.6		22.06		24.43		76.5		48.98		22.25		46
	<u> </u>															
	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water
Date	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation
11/04/93	NT	NT	6.24	634.62	7.08	633.28	16.44	676.78	70.75	646.05	39.38	677.25	16.35	700.3	42.05	650.94
11/23/93	5.60	634.82	6.05	634.81	7.24	633.12	16.94	676.28	57.04	659.76	48.94	667.69	16.72	699.93	42.30	650.69
12/09/93	5.64	634.78	6.10	634.76	7.53	632.83	17.20	676.02	53.54	663.26	40.76	675.87	17.15	699.5	NT	NT
12/16/93	6.22	634.2	7.71	633.15	7.62	632.74	17.49	675.73	52.57	664.23	41.05	675.58	17.70	698.95	NT	NT
01/20/94	5.97	634.45	6.40	634.46	8.46	631.9	18.05	675.17	50.95	665.85	52.57	664.06	18.50	698.15	42.26	650.73
10/28/99	6.80	633.62	7.20	633.66	10.10	630.26	18.60	674.62	45.95	670.85	41.95	674.68	19.70	696.95	NT	NT
09/30/2002	7.10	633.32	7.58	633.28	10.68	629.68	18.83	674.39	44.03	672.77	41.95	674.68	20.63	696.02	34.69	658.3
03/18/2003	6.70	633.72	7.15	633.71	9.20	631.16	19.08	674.14	44.80	672	42.55	674.08	21.15	695.5	34.40	658.59
09/04/2003	7.85	632.57	8.40	632.46	11.80	628.56	20.10	673.12	45.45	671.35	43.35	673.28	21.95	694.7	36.00	656.99
03/03/2004	7.40	633.02	7.90	632.96	10.35	630.01	20.45	672.77	45.80	671	43.85	672.78	21.90	694.75	35.80	657.19
09/04/2004	7.60	632.82	8.20	632.66	11:00	629.36	20.60	672.62	45.95	670.85	43.70	672.93	21.85	694.8	dry	dry
03/10/2005	7.20	633.22	7.70	633.16	10.15	630.21	20.35	672.87	45.80	671	43.45	673.18	21.60	695.05	dry	dry
09/08/2005	8.45	631.97	9.01	631.85	12.10	628.26	20.91	672.31	46.32	670.48	43.90	672.73	21.85	694.8	dry	dry
03/15/2006	7.65	632.77	8.17	632.69	9.52	630.84	20.98	672.24	46.26	670.54	44.18	672.45	21.86	694.79	dry	dry
09/27/2006	8.64	631.78	9.18	631.68	12.28	628.08	21.54	671.68	46.57	670.23	44.35	672.28	21.88	694.77	dry	dry
03/06/2007	7.60	632.82	8.00	632.86	8.10	632.26	21.60	671.62	47.10	669.7	44.70	671.93	21.98	694.67	34.70	658.29
10/15/2007	8.05	632.37	7.60	633.26	11.30	629.06	21.55	671.67	46.55	670.25	44.42	672.21	21.85	694.8	35.00	657.99
						-								,		
					-		-		-		-		-		-	
Average	7.15		7.56		9.68		19.45		49.14		43.83	}	20.27		37.47	
Std. Dev.	0.91		0.92		1.70		1.70		6.41		2.97		2.05		3.39	
	12.69%		12.15%		17.57%		8.72%		13.05%		6.78%		10.11%		9.03%	
Maximum	8.64		9.18		12.28		21.60		70.75		52.57		21.98		42.30	
Minimum	0.00		6.05		7.08		16.44		44.03		39.38		16.35		0.00	